



**NEW GENERATOR FOR
PHYSICAL PLANT, CORONER'S OFFICE AND ELECTION STORAGE**

AT

**CHAMPAIGN COUNTY PHYSICAL PLANT
202 ART BARTELL ROAD
URBANA, ILLINOIS 61802**

FOR

**COUNTY OF CHAMPAIGN
URBANA, ILLINOIS 61802**

**PROJECT MANUAL
ITB #2017-003**

May 4, 2017



TABLE OF CONTENTS

DIVISION 00 – PROCUREMENT AND CONTRACTING REQUIREMENTS

00 0200	NOTICE TO BIDDERS
00 1116	INVITATION TO BID
00 2213	SUPPLEMENTARY INSTRUCTIONS TO BIDDERS
00 4113	BID FORM – STIPULATED SUM (SINGLE-PRIME CONTRACT)
00 4313	BID SECURITY FORMS

DIVISION 01 – GENERAL REQUIREMENTS

01 1000	SUMMARY
01 2000	PRICE AND PAYMENT PROCEDURES
01 2500	SUBSTITUTION PROCEDURES
01 2500a	SUBSTITUTION REQUEST FORM
01 2600	CONTRACTOR MODIFICATION PROCEDURES
01 3000	ADMINISTRATIVE REQUIREMENTS
01 4000	QUALITY REQUIREMENTS
01 6000	PRODUCT REQUIREMENTS
01 7000	EXECUTION AND CLOSEOUT REQUIREMENTS
01 7419	CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

DIVISION 26 – ELECTRICAL

26 0519	LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES
26 0526	GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS
26 0529	HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS
26 0533	RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS
26 0544	SLEEVES AND SLEEVE SEALS FOR ELECTRICAL RACEWAYS AND CABLING
26 0553	IDENTIFICATION FOR ELECTRICAL SYSTEMS
26 3216	ENGINE GENERATORS
26 3600	TRANSFER SWITCHES

INDEX OF DRAWINGS

C-1	COVER SHEET
E-1	ELECTRICAL SITE PLAN – DEMOLITION
E-2	ELECTRICAL SITE PLAN – NEW WORK
E-3	ELECTRICAL FLOOR PLAN – DEMOLITION
E-4	ELECTRICAL FLOOR PLAN – NEW WORK
E-5	ELECTRICAL ONE LINE DIAGRAM – DEMOLITION
E-6	ELECTRICAL ONE LINE DIAGRAM – NEW WORK

END OF TABLE OF CONTENTS 00 0100



May 4, 2017

BID: County of Champaign, Illinois
New Generator for Physical Plant, Coroner's Office and Election Storage
THURSDAY, JUNE 1, 2017
2:30 P.M., Public Opening
Lyle Shields Conference Room
Brookens Administrative Center
1776 East Washington
Urbana, Illinois 61802-4581

Dear Bidder:

The County of Champaign is inviting the submission of sealed bids for New Generator for Physical Plant, Coroner's Office and Election Storage Project located at 202 Art Bartell Road, Urbana, Illinois.

Specifications are prepared with the intent of offering equal opportunity to all bidders. No oral interpretations will be given to any bidder as to the meaning of the specifications. Requests for clarification must be submitted **in writing** via mail, fax or email to:

GHR Engineers and Associates, Inc.
Attn.: Lucas McGill
1615 South Neil Street
Champaign, IL 61820
Fax: (217) 356-1092
Email: lmcgill@ghrinc.com

Clarification requests must be received no later than **Tuesday, May 30, 2017**, 12:00 noon to be considered.

Documents can be procured through Dean's Superior Blueprint Online Planroom.

Pursuant to the Illinois Prevailing Wage Act (820 ILCS 130/1 et seq.), not less than the prevailing rate of wages as determined by the Illinois Department of Labor, County of Champaign, or court on review shall be paid by the vendor/contractor to all laborers, workers and mechanics performing work under this purchase order.

All bids are to be sealed and in the hands of the undersigned by the due date and time stated above, at which time bids will be publicly opened. There will be no bids accepted after said date and time. Your bid is to be submitted on the bid form provided. The envelope containing your bid is to be sealed and marked in the lower left-hand corner: **"Sealed Bid: New Generator**



for Physical Plant, Coroner's Office and Election Storage". Bids will not be accepted by FAX mail.

The Champaign County Board reserves the right to reject any or all bids, to accept the bids, or to waive any irregularities should it deem to be in the best interest of the County of Champaign to do so. The bids will be awarded to the lowest responsible bidder meeting specifications as determined by the Champaign County Board.

Sincerely,

Dana Brenner
Facilities Director

END OF NOTICE TO BIDDERS 00 0200



DOCUMENT 00 1116 - INVITATION TO BID - #2017-003

1.1 PROJECT INFORMATION

- A. Notice to Bidders: Qualified bidders are invited to submit bids for Project as described in this Document.
- B. Project Identification: **New Generator for Physical Plant, Coroner's Office and Election Storage.**
 - 1. Project Location:

Champaign County Physical Plant
202 Art Bartell Road
Urbana, Illinois 61802
- C. Owner: County of Champaign
 - 1. Owner's Representative:

Dana Brenner, Facilities Director
1776 East Washington
Urbana, IL 61802-4581
Phone: (217) 384-3765
Fax: (217) 384-3896
Email: dbrenner@co-champaign.il.us
- D. Project Design Team: GHR Engineers and Associates, Inc.
- E. Project Description: Project consists of:
 - 1. Providing a new diesel generator and automatic transfer switch in order to provide emergency power to this entire building.
- F. Certification Contract: Bids will be received for the following Work:
 - 1. Single Prime Contract



1.2 BID SUBMITTAL AND OPENING

- A. Owner will receive sealed bids until the bid time and date at the location indicated below. Owner will consider bids prepared in compliance with the Contract Documents issued by Owner, and delivered as follows:

1. **Bid Date: Thursday, June 1, 2017.**
2. **Bid Time: 2:30 p.m., local time.**

Location:

Lyle Shields Meeting Room
Brookens Administration Center
1776 East Washington
Urbana, IL 61802

- B. Bids will be thereafter opened in the presence of the bidders and read aloud.

1.3 BID SECURITY

- A. Bid security in the form of a bank draft/cashier's check, certified check, U.S. money order, or bid bond **payable to County of Champaign** shall be submitted with each bid in the amount of **ten (10) percent** of the bid amount. No bids may be withdrawn for a period of **sixty (60) days** after opening of bids. Owner reserves the right to reject any and all bids and to waive informalities and irregularities.

1.4 PREBID CONFERENCE / SITE VISIT

- A. A vendor prebid conference for all bidders will be held at **Lyle Shields Conference Room, Brookens Administration Center, 1776 East Washington Street, Urbana, Illinois** on Thursday, May 18, 2017 at 2:00 pm, local time. Meet at front entrance. Prospective bidders are not required, but advised, to attend.
- B. Building access for additional site visits may be made by contacting Owner's Representative.

Dana Brenner, Facilities Director
Phone: 217-384-3765
Fax: 217-384-3896
E-mail: dbrenner@co-champaign.il.us



1.5 DOCUMENTS

- A. Documents can be procured through Dean's Superior Blueprint Online Planroom: <https://www.deansplanroom.com/>.

1.6 TIME OF COMPLETION

- A. Bidders shall begin the Work on receipt of the Notice to Proceed and shall complete the Work within the Contract Time.
1. Anticipated Award of Contract: Board Meeting, **June 23, 2017**.
 2. Anticipated Letter of Notice of Award: On or about **June 24, 2017**.
 3. Pre-Construction/Pre-Installation Meeting: TBD.
 4. **Substantial Completion: September 26, 2017.**
 5. Punch List: Issued on or about **September 27, 2017**.
 6. **Final Completion: October 10, 2017.**

1.7 BIDDER'S QUALIFICATIONS

- A. Bidders must be properly licensed under the laws governing their respective trades and be able to obtain insurance and bonds required for the Work. **A Performance Bond, a separate Labor and Material Payment Bond, and Insurance in a form acceptable to Owner will be required of the successful Bidder.**

1.8 EXAMINATION

- A. Bidders shall tour the project location to familiarize themselves with the locations of existing equipment to include all the cost of demo and new work as shown on the drawings.

END OF DOCUMENT 00 1116



DOCUMENT 00 2213 - SUPPLEMENTARY INSTRUCTIONS TO BIDDERS

1.1 SUPPLEMENTARY INSTRUCTIONS TO BIDDERS - BIDDER'S REPRESENTATIONS

- A. The Bidder has investigated all required fees, permits, and regulatory requirements of authorities having jurisdiction and has properly included in the submitted bid the cost of such fees, permits, and requirements not otherwise indicated as provided by Owner.
 - 1. Permit Application: Complete building permit application and file with authorities having jurisdiction within five days of the Notice of Award.
- B. The Bidder is a properly licensed Contractor according to the laws and regulations of The State of Illinois and meets qualifications indicated in the Procurement and Contracting Documents.
- C. The Bidder has incorporated into the Bid adequate sums for work performed by installers whose qualifications meet those indicated in the Procurement and Contracting Documents.

1.2 BIDDING DOCUMENTS

- A. Interpretation or Correction of Procurement and Contracting Documents:
 - 1. Submit Bidder's Requests for Interpretation as outlined in the Notice to Bidders.
- B. Submit Requests for Substitution on form provided. Substitution requests shall be in advance of bid.
- C. Addenda:
 - 1. Addenda may be issued at any time prior to the receipt of bids.
 - 2. Owner may elect to waive the requirement for acknowledging receipt of Addenda as follows:
 - a. Information received as part of the Bid indicates that the Bid, as submitted, reflects modifications to the Procurement and Contracting Documents included in an unacknowledged Addendum.



- b. Modifications to the Procurement and Contracting Documents in an unacknowledged Addendum do not, in the opinion of Owner, affect the Contract Sum or Contract Time.

1.3 BIDDING PROCEDURES

A. Preparation of Bids:

1. The Bid shall include unit prices when called for by the Procurement and Contracting Documents. Owner may elect to consider unit prices in the determination of award. Unit prices will be incorporated into the Contract.
2. Owner may elect to disqualify a bid due to failure to submit a bid in the form requested, failure to bid requested alternates or unit prices, failure to complete entries in all blanks in the Bid Form, or inclusion by the Bidder of any alternates, conditions, limitations or provisions not called for.

Retail sales tax will NOT be included in the bid amount. The Owner is exempted by Section 3 of the Illinois Use Tax Act (Section 3, House Bill 1610, approved July 31, 1961, Illinois Revised Statutes 1967, Chapter 120, Section 439.3) from paying any of the taxes imposed by the Act and sales to Owner are exempt by Section 2, House Bill 1609, approved July 31, 1961, Illinois Revised statutes 1967, Chapter 120, Section 441) from any of the taxes imposed by the Act. The Department of Revenue of the State of Illinois under Rule No. 15, issued August 9, 1961, has declared that sales of materials to construction contractors for conversion into real estate for schools, governmental bodies, agencies and instrumentalities are not taxable retail sales. **The Contractor shall be responsible for any sales, consumer, use and similar taxes for the Work.**

3. Owner is not responsible for any costs incurred by a Contractor in the preparation or delivery of bids. The Contractor shall be responsible for the actual delivery of bids during business hours to the address indicated. Any bid received after the delivery deadline will be disqualified.
4. Owner reserves the right to obtain clarification of any point in a Contractor submittal or to obtain additional information.

FOIA: As an independent Contractor of the District, records in the possession of the Contractor related to this Agreement may be subject to the Illinois Freedom of Information Act ("FOIA"), 5 ILCS 140/5-1 et seq.; 5 ILCS 140/7(2). The Contractor shall immediately provide the District with any such records



requested by the District in order to timely respond to any FOIA request received by the District.

B. Subcontractors, Suppliers, and Manufacturers List Bid Supplement:

1. Provide list of major subcontractors, suppliers, and manufacturers furnishing or installing products no later than **ten (10) business days** following Notice to Proceed. Do not change subcontractors, suppliers, and manufacturers from those submitted without approval of Owner.

1.4 CONSIDERATION OF BIDS

A. Rejection of Bids:

Owner reserves the right to reject a bid based on Owner's and Design Team's evaluation of qualification information submitted following opening of bids. Owner's evaluation of the Bidder's qualifications will include: status of licensure and record of compliance with licensing requirements, record of quality of completed work, record of Project completion and ability to complete, record of financial management including financial resources available to complete Project and record of timely payment of obligations, record of Project site management including compliance with requirements of authorities having jurisdiction, record of and number of current claims and disputes and the status of their resolution, and qualifications of the Bidder's proposed Project staff and proposed subcontractors.

1.5 PERFORMANCE BOND AND PAYMENT BOND

- A. Both a Performance Bond and a Payment Bond will be required, each in an amount equal to 100 percent of the Contract Sum.
- B. The Bidder shall deliver the required bonds to Owner no later than **ten (10) days** after the date of Notice of Intent to Award and no later than the date of execution of the Contract, whichever occurs first. Owner may deem the failure of the Bidder to deliver required bonds within the period of time allowed a default.
- C. Bonds shall be executed and be in force on the date of the execution of the Contract.



1.6 INSURANCE

GENERAL The successful bidder shall maintain for the duration of the contract and any extensions thereof, at bidder's expense, insurance that includes "Occurrence" basis wording and is issued by a company or companies qualified to do business in the State of Illinois that are acceptable to the County, which generally requires that the company(ies) be assigned a Best's Rating of A or higher with a Best's financial size category of Class A-/VII or higher, in the following types and amounts:

1. Commercial General Liability in a broad form, to include, but not limited to, coverage for the following where exposure exists: Bodily Injury and Property Damage, Premises/Operations, Independent contractors, Products/Completed Operations, Personal Injury and Contractual Liability; limits of liability not less than: \$1,000,000 per occurrence and \$2,000,000 in the aggregate, and inclusion of a waiver of subrogation in favor of Champaign County;
2. Business Auto Liability to include, but not be limited to, coverage for the following where exposure exists: Owned Vehicles, Hired and Non-Owned Vehicles and Employee Non-Ownership; limits of liability not less than: \$1,000,000 per occurrence, combined single limit for: Bodily Injury Liability and Property Damage Liability;
3. Workers' Compensation Insurance to cover all employees and meet statutory limits in compliance with applicable state and federal laws. The coverage must also include Employer's Liability with minimum limits of \$500,000 for each incident, \$500,000 for each disease and \$500,000 aggregate, and a waiver of subrogation in favor of Champaign County.

B. EVIDENCE OF INSURANCE The successful bidder agrees that with respect to the above required insurance that:

1. The County of Champaign shall be provided with Certificates of Insurance evidencing the above required insurance, prior to commencement of the contract and thereafter with certificates evidencing renewals or replacements of said policies of insurance at least fifteen (15) days prior to the expiration or cancellation of any such policies;
2. The contractual liability arising out of the contract shall be acknowledged on the Certificate of Insurance by the insurance company;
3. The County of Champaign shall be provided with thirty (30) days prior notice, in writing, of Notice of Cancellation or material change and said notification requirement shall be stated on the Certificate of Insurance;
4. Subcontractors, if any, shall execute the Subcontractor Agreement provided by Champaign County, and comply with the same insurance requirements as contractors.



5. In addition to being named as an additional insured on the Certificate of Insurance, each liability policy shall contain an endorsement naming the County of Champaign as an additional insured. A copy of the endorsement shall be provided to Champaign County along with the Certificate of Insurance; and,
6. Champaign County must be named as an additional insured, on a primary and noncontributory basis, and the address for certificate holder must read exactly as: County of Champaign, a body politic 1776 East Washington Street, Urbana, IL 61802
7. Insurance Notices and Certificates of Insurance shall be provided to: Champaign County, Insurance Specialist, Administrative Services Department, 1776 East Washington Street, Urbana, IL 61802

1.7 STANDARD CONTRACT CONDITIONS

- A. This contract shall be governed in all aspects as to validity, construction, capacity, performance, or otherwise by the laws of the State of Illinois.
- B. Contractors shall comply with the Civil Rights Act of 1964, as amended, all applicable State and Federal non-discrimination laws including but not limited to the Family and Medical Leave Act, the Americans with Disabilities Act, the Age Discrimination in Employment Act and shall comply with the provisions of the Illinois Human Rights Act.
- C. Contractors shall not assign, transfer, convey, sublet, or otherwise dispose of this contract, including any or all of its right, title or interest therein, or its power to execute such contract to any person, company or corporation, without prior written consent of The County of Champaign.
- D. By submitting a bid the Contractor certifies that the Contractor is not barred from bidding on this contract as a result of a violation of either the bid-rigging or bid-rotating provisions of Article 33E of the Criminal Code of 1961, as amended.

By submitting a bid, the Contractor, having 25 or more employees, does hereby certify pursuant to Section 3 of the Illinois Drug-Free Workplace Act (30 ILCS 580/3) that it shall provide a drug-free workplace for all employees engaged in the performance of work under the contract by complying with the requirements of the Illinois Drug-Free Workplace Act and, further certifies, that it is not ineligible for award of this contract by reason of debarment for a violation of the Illinois Drug-Free Workplace Act.

- E. By submitting a bid, the Contractor does hereby certify pursuant to Section 2-105 of the Illinois Human Rights Act (775 ILCS 5/2-105) that it has a written sexual harassment policy that includes, at a minimum, the following information: (i) the illegality of sexual harassment; (ii) the definition of sexual harassment under State law; (iii) a



description of sexual harassment, utilizing examples; (iv) an internal complaint process including penalties; (v) the legal recourse, investigative and complaint process available through the Department of Human Rights and Human Rights Commission; (vi) direction on how to contact the Department of Human Rights and Human Rights Commission; and (vii) protection against retaliation.

1.8 STATEMENT OF NON-DISCRIMINATION

- A. The Illinois Human Rights Acts prohibits discrimination on the basis of: “race, color, religion, sex, national origin, ancestry, age, order of protection status, marital status, physical or mental disability, military status, sexual orientation, or unfavorable discharge from military service in connection with employment, real estate transactions, access to financial credit, and the availability of public accommodations.” It also prohibits sexual harassment and discrimination in employment on the basis of citizenship status.

1.9 PREVAILING WAGE

- A. This contract calls for the construction of a “public work” within the meaning of the Illinois Prevailing Wage Act, 920 ILCS 130/.01. The Act requires contractors and subcontractors to pay all laborers, workers and mechanics performing services on public works projects no less than the “prevailing rate of wages” (hourly cash wages plus fringe benefits) in the county where the work is performed. Each Contractor and Subcontractor rendering services under this contract must comply with all requirements of this Act. Each Contractor and Subcontractor shall keep records of the prevailing wages paid to their employees, submit a monthly certified payroll to County of Champaign, and make such records available to County of Champaign for inspection upon seven business days notice.
- B. For information regarding the current prevailing wage rates for Champaign County, Illinois can be found at:
- <http://www.illinois.gov/idol/laws-rules/conmed/pages/rates.aspx>.
- C. Prevailing Wage Rates change periodically. Contractor shall verify and revise the prevailing wages on a regular basis.

1.10 FAILURE TO FULFILL CONTRACT

- A. When any Contractor fails to provide a service or provides a service which does not conform to the specifications, County of Champaign may, at its sole discretion, annul



and set aside the contract entered into with said Contractor, either in whole or in part, and make and enter into a new contract for the same services in such manner as seems to County of Champaign to be to its best advantage. Any failure to furnish services by reason of the failure of the Contractor, as stated above, shall be a liability against such Contractor and his sureties. County of Champaign reserves the right to cancel, without penalty, any services which the successful Contractor may be unable to furnish because of economic conditions, governmental regulations or other similar causes beyond the control of the Contractor provided satisfactory proof is furnished to County of Champaign if requested.

Without Cause Termination: The County may terminate its contract with the Contractor without cause after providing the Contractor with thirty (30) days written notice.

1.11 EXECUTION OF THE CONTRACT

- A. Subsequent to the Notice of Intent to Award, and within **ten (10) business days** after the prescribed Form of Agreement is presented to the Awardee for signature, the Awardee shall execute and deliver the Agreement to Owner through Engineer, in such number of counterparts as Owner may require.
- B. Owner may deem as a default the failure of the Awardee to execute the Contract and to supply the required bonds and insurance when the Agreement is presented for signature within the period of time allowed.
- C. Unless otherwise indicated in the Procurement and Contracting Documents of the executed Agreement, the date of commencement of the Work shall be the date of the executed Agreement.
In the event of a default, Owner may declare the amount of the Bid security forfeited and elect to either award the Contract to the next responsible bidder or re-advertise for bids.

1.12 INDEMNITY

- A. To the fullest extent permitted by law, Contractor shall indemnify and hold harmless the Owner from and against claims, damages, losses and expenses, including but not limited to attorney's fees, arising out of or resulting from performance of the work provided that such claim, damage, loss or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property, but only to the extent caused by the negligent acts or omissions of the Contractor, a subcontractor, anyone directly or indirectly employed by them or anyone for whose



acts they may be liable, regardless of whether or not such claim damage, loss or expense is caused in part by a party indemnified hereunder.

END OF DOCUMENT 00 2213



DOCUMENT 00 4113 - BID FORM - STIPULATED SUM (SINGLE-PRIME CONTRACT)

1.1 BID INFORMATION

- A. Bidder: _____.
- B. Project Name: **New Generator for Physical Plant, Coroner's Office and Election Storage Project**
- C. Project Location: Champaign County Physical Plant
202 Art Bartell Road
Urbana, Illinois 61802
- D. Owner: County of Champaign
- E. Building Design Team: GHR Engineers and Associates, Inc.

1.2 CERTIFICATIONS AND BASE BID

- A. Base Bid, Single-Prime (All Trades) Contract: The undersigned Bidder, having carefully examined the Procurement and Contracting Requirements, Conditions of the Contract, Drawings, Specifications, and all subsequent Addenda, as prepared by the Design Team, having visited the site, and being familiar with all conditions and requirements of the Work, hereby agrees to furnish all material, labor, equipment and services, including all scheduled allowances, necessary to complete the construction of the above-named project, according to the requirements of the Procurement and Contracting Documents, for the stipulated sum of:

Base Bid

- 1. _____ Dollars (\$_____).

1.3 BID GUARANTEE

- A. The undersigned Bidder agrees to execute a contract for this Work in the above amount and to furnish surety as specified within **ten (10)** days after a written Notice of Award, if offered within **sixty (60)** days after receipt of bids, and on failure to do so agrees to forfeit to Owner the attached bank draft/cashier's check, certified check, U.S. money order, or bid bond **payable to County of Champaign**, as liquidated damages for such failure, in an amount constituting **ten percent (10%)** of the Base Bid amount:



Base Bid

1. _____ Dollars (\$_____).

- B. In the event Owner does not offer Notice of Award within the time limits stated above, Owner will return to the undersigned the bank draft/cashier's check, certified check, U.S. money order, or bid bond.

1.4 SUBCONTRACTORS AND SUPPLIERS

- A. The following companies shall execute subcontracts for the portions of the Work indicated:

1. General Work: _____.
2. Electrical Work: _____.
3. Plumbing Work: _____.
4. Fire Protection Work: _____.

1.5 TIME OF COMPLETION

- A. The undersigned Bidder proposes and agrees hereby to commence the Work of the Contract Documents on a date specified in a written Notice to Proceed to be issued by Owner, and shall fully complete the Work as indicated in the Invitation to Bid.

1.6 ACKNOWLEDGEMENT OF ADDENDA

- A. The undersigned Bidder acknowledges receipt of and use of the following Addenda in the preparation of this Bid:
1. Addendum No. 1, dated _____.
 2. Addendum No. 2, dated _____.
 3. Addendum No. 3, dated _____.

1.7 CONTRACTOR'S LICENSE

- A. The undersigned warrants that he/she is duly authorized to bind contractually the entity submitting this bid, to fully perform all duties and to deliver all services in accordance with the terms and conditions set forth herein. All signatures to be sworn before a Notary Public.



1.8 SUBMISSION OF BID

Respectfully submitted this ____ day of _____, 2017.

Submitted By: _____
(Name of bidding firm or corporation)

Authorized
Signature: _____
(Handwritten signature)

Signed By: _____
(Type or print name)

Title: _____
(Owner/Partner/President/Vice President)

Witness By: _____
(Handwritten signature)

Attest: _____
(Handwritten signature)

By: _____
(Type or print name)

Subscribed and sworn to before me this

_____ Day of _____, 2017.

_____, Notary Public

(Affix Notary Seal Here)

END OF DOCUMENT 00 4113



DOCUMENT 00 4313 - BID SECURITY FORMS

1.1 BID FORM SUPPLEMENT

- A. A completed bid bond form is required to be attached to the Bid Form.

1.2 BID BOND FORM

- A. AIA Document A310, "Bid Bond," is the recommended form for a bid bond. A bid bond acceptable to Owner, is required to be attached to the Bid Form as a supplement.
- B. Copies of AIA standard forms may be obtained from The American Institute of Architects; www.aia.org/contractdocs/purchase/index.htm; email: docspurchases@aia.org; (800) 942-7732.

END OF DOCUMENT 00 4313



SECTION 01 1000 - SUMMARY

PART 1 - GENERAL

1.1 PROJECT INFORMATION

A. Project Identification: **New Generator for Physical Plant, Coroner's Office and Election Storage**

1. Project Location:

Champaign County Physical Plant
202 Art Bartell Road
Urbana, Illinois 61802

B. Owner: County of Champaign

C. Design Team: GHR Engineers and Associates, Inc.

D. Project consists providing a new diesel generator and automatic transfer switch in order to provide emergency power to this entire building.

1.2 WORK RESTRICTIONS

A. Contractor's Use of Premises: During construction, Contractor will have limited use of site and building indicated. Contractor's use of premises is limited only by Owner's right to perform work or employ other contractors on portions of Project and as follows:

1. First subparagraph below contains an example of limitations on Contractor's use of premises; delete if not applicable. Insert other descriptions of areas or types of limited use, requirements for cooperation with Owner's personnel, noninterference with Owner's or public use, and other necessary restrictions if required.
2. Owner will occupy premises during construction. Perform construction only during normal working hours 8 AM to 5 PM Monday thru Friday, other than holidays, unless otherwise agreed to in advance by Owner. Clean up work areas and return to usable condition at the end of each work period.
3. Limits: Limit site disturbance.



4. Driveways, Walkways, and Entrances: Keep driveways, loading areas, and entrances serving premises clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.
- B. On-Site Work Hours: Limit work in the existing building to normal business working hours of 8 AM to 5 PM, Monday through Friday, unless otherwise indicated.
 1. Weekend Hours: As permitted by Owner. Coordinate with Owner.
 2. Early Morning Hours: 7 AM or as permitted by Owner. Coordinate with Owner.
- C. Nonsmoking Building: Smoking is not permitted within the building or on the project site.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 1000



SECTION 01 2000 - PRICE AND PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 PAYMENT PROCEDURES

- A. Submit a Schedule of Values at least **seven (7)** days before the initial Application for Payment. Break down the Contract Sum into at least one line item for each Specification Section in the Project Manual table of contents. Coordinate the schedule of values with Contractor's construction schedule.
 - 1. Arrange schedule of values consistent with format of AIA Document G703.
 - 2. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
 - 3. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
 - 4. Provide separate line items in the schedule of values for initial cost of materials and for total installed value of that part of the Work.
 - 5. Provide a separate line item in the schedule of values for each allowance.
- B. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 forms for Applications for Payment.
 - 1. Anticipated Application for Payment Schedule:
 - a. Application for Payment No. 01: once material is delivered to project site
 - b. Application for Payment No. 02: upon completion of installation
 - c. Application for Payment No. 03: Final payment upon completion of punch list, receipt of all close-out documents and completion of owner training
- C. Submit **three (3)** copies of each application for payment according to the schedule established in Owner/Contractor Agreement.
 - 1. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor.
 - 2. With each Application for Payment, Contractor shall include the Contractor's waiver of lien for the full amount and partial waivers of mechanic's liens from subcontractors, sub-subcontractors, and suppliers for construction period covered by the previous application.



3. Submit final Application for Payment with or preceded by conditional final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
 - a. Include insurance certificates, proof that taxes, fees, and similar obligations were paid, and evidence that claims have been settled.
 - b. Include affidavit of payment of debts and claims on AIA Document G706.
 - c. Include affidavit of release of liens on AIA Document G706A.
 - d. Include consent of surety to final payment on AIA Document G707.
4. Certified Payroll Statements: The Contractor shall submit Certified Payroll Statements pursuant to Illinois Law-Public Act 94-0515 with each payment application. The *Certified Transcript of Payroll* statement forms are available through the Illinois Department of Labor website:
<http://www.state.il.us/agency/idol/forms/pdfs/IL452CM02.pdf>.
Certified payroll statements are required from the Contractor and each Subcontractor. The statements are to include the time period of the payment application. Payment Applications will not be processed without accompanying Certified Payroll Statements.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 2000



SECTION 01 2500 - SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 SUBSTITUTION PROCEDURES

- A. Substitutions include changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.
- B. Substitution Requests: Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles. Substitutions will NOT be considered after bidding.
 - 1. Substitution Request Form: Use facsimile of form provided in the Project Manual.
 - 2. Submit requests by noon on May 31, 2017.
 - 3. Identify product to be replaced and show compliance with requirements for substitutions. **Include a detailed comparison of significant qualities of proposed substitution with those of the Work specified**, a list of changes needed to other parts of the Work required to accommodate proposed substitution, and any proposed changes in the Contract Sum or the Contract Time should the substitution be accepted.
 - 4. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
 - a. Statement indicating why specified product or fabrication or installation cannot be provided, if applicable.
 - b. Coordination information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors that will be necessary to accommodate proposed substitution.
 - c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. **Indicate deviations, if any, from the Work specified.**
 - d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.



- e. Samples, where applicable or requested:
 - 1) All samples shall be clearly labeled with product information and Vendor contact information.
 - f. Certificates and qualification data, where applicable or requested.
 - g. List of similar installations for completed projects with project names and addresses and names and addresses of engineers and owners.
 - h. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
 - i. Research reports evidencing compliance with building code in effect for Project.
 - j. Detailed comparison of Contractor's construction schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
 - k. Cost information, including a proposal of change, if any, in the Contract Sum.
 - l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.
 - m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
- C. Engineer will review proposed substitutions and notify Contractor of their acceptance or rejection via Addendum. If necessary, Engineer will request additional information or documentation for evaluation.
- 1. Use product specified if Engineer does not issue a decision on use of a proposed substitution within time allocated.
- D. Do not submit unapproved substitutions on Shop Drawings or other submittals.



PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 2500



SUBSTITUTION REQUEST FORM

Project: NEW GENERATOR FOR PHYSICAL PLANT, CORONER'S
OFFICE AND ELECTION STORAGE

Request No.:

Date:

Location (provide room number(s):

Name of Material, Product or Equipment item specified:

Name of Material, Product or Equipment item submitted as substitution:

Specification Section:

Qualities that differ from specified product or system:

Name of Manufacturer / Fabricator:

Address

City, State and Zip

Phone:

Name of Vendor / Supplier Requesting Change	Address	Contact Name	Phone:

Reason for requesting substitution request:

Substitution affects other materials or systems, such as dimensional revisions, redesign of structure or modifications to other work:

_____ NO

_____ YES; describe requirements:



If substitution requires modifications to dimensions indicated on drawings, are such modifications clearly indicated on attached data?

_____ YES

_____ NO; if NO, explain:

Substitution has an affect on Construction Schedule:

_____ NO

_____ YES; describe affect on schedule:

Savings or Credit to Contract Amount for accepting substitute:

_____ Dollars (\$_____).

Note: Show bid amount in both words and figures.

The attached data is furnished herewith for evaluation of the substitution:

_____ Product Data _____ Drawings _____ Samples _____ Tests _____ Reports

_____ Other Information; describe:

The undersigned hereby certifies:

1. The proposed substitution has been fully investigated and is equal or superior to specified product.
2. The same or better warranty will be furnished for proposed substitution as for specified material, product or equipment.
3. All changes in the work resulting from the use of this substitution, if approved, will be coordinated and completed in all respects and all costs, including, but not limited to, those for additional services rendered by the Owner are the responsibility for this Contractor at no additional cost to the Contract.

Contractor

Signed by

Address

City, State and Zip

END OF SUBSTITUTION FORM 01 2500a



SECTION 01 2600 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 CONTRACT MODIFICATION PROCEDURES

- A. Design Team will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time.
- B. Owner-Initiated Proposal Requests: Design Team will issue a detailed description of proposed changes in the Work.
 - 1. Proposal Requests are not instructions either to stop work in progress or to execute the proposed change.
 - 2. Within time specified in Proposal Request or 20 days, when not otherwise specified, after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time.
- C. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Design Team.
- D. On Owner's approval of a Proposal Request, Design Team will issue a Change Order for signatures of Owner and Contractor, for all changes to the Contract Sum or the Contract Time.
- E. Design Team may issue a Construction Change Directive. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
 - 1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- F. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.



PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 2600



SECTION 01 3000 - ADMINISTRATIVE REQUIREMENTS

PART 1 - GENERAL

1.1 PROJECT MANAGEMENT AND COORDINATION

- A. Subcontract List: Submit a written summary identifying individuals or firms proposed for each portion of the Work.
- B. Key Personnel Names: Within ten (10) days of starting construction operations, submit a list of key personnel assignments, including superintendent and other personnel in attendance at Project site. List e-mail addresses and telephone numbers.
- C. Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work.
- D. Requests for Information (RFIs): On discovery of the need for additional information or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI. Use forms acceptable to Design Team and Owner.
- E. Schedule and conduct (2) progress meetings at Project site, coordinated with the Design Team and Owner. **Notify Owner of meeting dates and times.** Require attendance of each subcontractor or other entity concerned with current progress or involved in planning, coordination, or performance of future activities.

1.2 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

- A. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 - 1. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
 - 2. Submit two copies of each action submittal. Design Team will return one copy.
 - 3. Submit one copy of each informational submittal. Design Team will not return copies.
 - 4. Design Team will discard submittals received from sources other than Contractor.



- B. Electronic Submittals: Identify and incorporate information in each electronic submittal file as follows:
 - 1. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
 - 2. Name file with unique identifier, including project identifier, Specification Section number, and revision identifier.
 - 3. Provide means for insertion to permanently record Contractor's review and approval markings and action taken by Design Team.
- C. Identify options requiring selection by Design Team.
- D. Identify deviations from the Contract Documents on submittals.
- E. Contractor's Construction Schedule Submittal Procedure:
 - 1. Submit required submittals in the following format:
 - a. PDF electronic file.
 - 2. Coordinate Contractor's construction schedule with the schedule of values, submittal schedule, progress reports, payment requests, and other required schedules and reports.

PART 2 - PRODUCTS

2.1 SUBMITTAL PROCEDURES

- A. General Submittal Procedure Requirements: Prepare and submit submittals required by individual Specification Sections.
 - 1. Submit electronic submittals via email as PDF electronic files to Shannon Hicks at GHR Engineers and Associates, Inc.: shicks@ghrinc.com.
 - a. Design Team will return annotated file. Annotate and retain one copy of file as an electronic Project record document file.

2.2 ACTION SUBMITTALS

- A. Submit two paper copies of each submittal unless otherwise indicated. Design Team will return one copy.



- B. Product Data: Mark each copy to show applicable products and options. Include the following:
1. Manufacturer's written recommendations, product specifications, and installation instructions.
 2. Wiring diagrams showing factory-installed wiring.
 3. Printed performance curves and operational range diagrams.
 4. Testing by recognized testing agency.
 5. Compliance with specified standards and requirements.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data. Submit on sheets at least 8-1/2 by 11 inches but no larger than 30 by 42 inches. Include the following:
1. Dimensions and identification of products.
 2. Fabrication and installation drawings and roughing-in and setting diagrams.
 3. Wiring diagrams showing field-installed wiring.
 4. Notation of coordination requirements.
 5. Notation of dimensions established by field measurement.

2.3 INFORMATIONAL SUBMITTALS

- A. Informational Submittals: Submit one paper copy of each submittal unless otherwise indicated. Design Team will not return copies.
- B. Qualification Data: Include lists of completed projects with project names and addresses, names and addresses of Design Team and owners, and other information specified.
- C. Product Certificates: Prepare written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.

PART 3 - EXECUTION

3.1 SUBMITTAL REVIEW

- A. Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Design Team.



- B. Design Team will review each action submittal, make marks to indicate corrections or modifications required, will stamp each submittal with an action stamp, and will mark stamp appropriately to indicate action.
- C. Informational Submittals: Design Team will review each submittal and will not return it, or will return it if it does not comply with requirements. Design Team will forward each submittal to appropriate party.
- D. Submittals not required by the Contract Documents may not be reviewed and may be discarded.

END OF SECTION 01 3000



SECTION 01 4000 - QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 SECTION REQUIREMENTS

- A. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
- B. Referenced Standards: If compliance with two or more standards is specified and the standards establish different or conflicting requirements, comply with the most stringent requirement. Refer uncertainties to Design Team for a decision.
- C. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum. The actual installation may exceed the minimum within reasonable limits. Indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Design Team for a decision.
- D. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:
 - 1. Date of issue.
 - 2. Project title and number.
 - 3. Name, address, and telephone number of testing agency.
 - 4. Dates and locations of samples and tests or inspections.
 - 5. Names of individuals making tests and inspections.
 - 6. Description of the Work and test and inspection method.
 - 7. Identification of product and Specification Section.
 - 8. Complete test or inspection data.
 - 9. Test and inspection results and an interpretation of test results.
 - 10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
 - 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
 - 12. Name and signature of laboratory inspector.
 - 13. Recommendations on retesting and reinspecting.



- E. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, notices, receipts for fee payments, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.
- F. Testing Agency Qualifications: An independent agency with the experience and capability to conduct testing and inspecting indicated; and where required by authorities having jurisdiction, that is acceptable to authorities.
- G. Retesting / Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced work that failed to comply with the Contract Documents.
- H. Testing Agency Responsibilities: Cooperate with Design Team and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
 - 1. Notify Design Team and Contractor of irregularities or deficiencies in the work observed during performance of its services.
 - 2. Do not release, revoke, alter or increase requirements of the Contract Documents or approve or accept any portion of the work.
 - 3. Do not perform any duties of Contractor.
- I. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
 - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.
- J. Tests and Inspections: Owner will engage a qualified inspector to conduct inspections required by authorities having jurisdiction.

PART 2 - PRODUCTS (Not Used)



PART 3 - EXECUTION

3.1 REPAIR AND PROTECTION

- A. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.
- B. Contractor will maintain a safe work site at all times. When the project is complete, Contractor shall return the work site and the surrounding areas to the same condition as they were prior to the beginning of the project.

END OF SECTION 01 4000



SECTION 01 6000 - PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 SECTION REQUIREMENTS

- A. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
- B. Comparable Product Requests: Submit request for consideration of each comparable product. Identify product or fabrication or installation method to be replaced.
 - 1. Show compliance with requirements for comparable product requests.
 - 2. Design Team will review the proposed product and notify Contractor of its acceptance or rejection.
- C. Basis-of-Design Product Specification Submittal: Show compliance with requirements.
- D. Compatibility of Options: If Contractor is given option of selecting between two or more products, select product compatible with products previously selected.
- E. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft. Comply with manufacturer's written instructions.
 - 1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
 - 2. Deliver products to Project site in manufacturer's original sealed container or packaging, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
 - 3. Inspect products on delivery to ensure compliance with the Contract Documents and to ensure that products are undamaged and properly protected.
 - 4. Store materials in a manner that will not endanger Project structure.
 - 5. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
- F. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers



and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

- A. Provide products that comply with the Contract Documents, are undamaged, and, unless otherwise indicated, are new at the time of installation.
 - 1. Provide products complete with accessories, trim, finish, and other devices and components needed for a complete installation and the intended use and effect.
 - 2. Where products are accompanied by the term "as selected," Owner will make selection.
 - 3. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.
- B. Where the following headings are used to list products or manufacturers, the Contractor's options for product selection are as follows:
 - 1. Products:
 - a. Where requirements include "one of the following," provide one of the products listed that complies with requirements.
 - b. Where requirements do not include "one of the following," provide one of the products listed that complies with requirements or a comparable product.
 - 2. Manufacturers:
 - a. Where requirements include "one of the following," provide a product that complies with requirements by one of the listed manufacturers.
 - b. Where requirements do not include "one of the following," provide a product that complies with requirements by one of the listed manufacturers or another manufacturer.
 - 3. Basis-of-Design Product: Provide the product named, or indicated on the Drawings, or a comparable product by one of the listed manufacturers.



2.2 COMPARABLE PRODUCTS

- A. Design Team will consider Contractor's request for comparable product in advance of Bidding only when the following conditions are satisfied:
1. Evidence that the proposed product does not require revisions to the Contract Documents, that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
 2. Detailed comparison of significant qualities of proposed product with those named in the Specifications.
 3. List of similar installations for completed projects, if requested.
 4. Samples, where applicable.

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 6000



SECTION 01 7000 - EXECUTION AND CLOSEOUT REQUIREMENTS

PART 1 - GENERAL

1.1 EXECUTION REQUIREMENTS

A. Cutting and Patching:

1. Structural Elements: When cutting and patching structural elements, notify Design Team of locations and details of cutting and await directions from Engineer before proceeding. Shore, brace, and support structural elements during cutting and patching.
2. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety.
3. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Engineer's opinion, reduce the building's aesthetic qualities.

- B. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of products and equipment.

1.2 CLOSEOUT SUBMITTALS

- A. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.
- B. Certified List of Incomplete Items: Final submittal at Final Completion.
- C. Operation and Maintenance Data: Submit two (2) copies of manual.
- D. PDF Electronic File: Assemble manual into a composite electronically indexed file. Submit two (2) copies on digital media.
- E. Record Product Data: Submit two (2) paper copies and annotated PDF electronic files and directories of each submittal.



1.3 SUBSTANTIAL COMPLETION PROCEDURES

- A. Prepare a list of items to be completed and corrected (punch list), the value of items on the list, and reasons why the Work is not complete.
- B. Submittals Prior to Substantial Completion: Before requesting Substantial Completion inspection, complete the following:
 - 1. Submit closeout submittals specified in other sections, including project record documents, operation and maintenance manuals, similar final record information, warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
 - 2. Submit maintenance material submittals specified in other sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by Owner.
 - 3. Submit test/adjust/balance records.
- C. Procedures Prior to Substantial Completion: Before requesting Substantial Completion inspection, complete the following:
 - 1. Complete startup and testing of systems and equipment.
 - 2. Perform preventive maintenance on equipment used prior to Substantial Completion.
 - 3. Remove temporary facilities and controls.
 - 4. Complete final cleaning requirements, including touchup painting.
 - 5. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.
- D. Inspection: Submit a written request for inspection for Substantial Completion. On receipt of request, Engineer will proceed with inspection or advise Contractor of unfulfilled requirements. Engineer will prepare the Certificate of Substantial Completion after inspection or will advise Contractor of items that must be completed or corrected before certificate will be issued.

1.4 FINAL COMPLETION PROCEDURES

- A. Submittals Prior to Final Completion: Before requesting inspection for determining final completion, complete the following:
 - 1. Submit a final Application for Payment.



2. Submit certified copy of Engineer's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Engineer. Certified copy of the list shall state that each item has been completed or otherwise resolved.
- B. Submit a written request for final inspection for acceptance. On receipt of request, Design Team will either proceed with inspection or notify Contractor of unfulfilled requirements. Engineer will prepare final Certificate for Payment after inspection or will advise Contractor of items that must be completed or corrected before certificate will be issued.
1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.
- B. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.
1. Use cleaning products that comply with Green Seal's GS-37, or if GS-37 is not applicable, use products that comply with the California Code of Regulations maximum allowable VOC levels.

2.2 OPERATION AND MAINTENANCE DOCUMENTATION

- A. Directory: Prepare a single, comprehensive directory of operation and maintenance data and materials, listing items and their location to facilitate ready access to desired information.
- B. Organization: Unless otherwise indicated, organize manual into separate sections for each system and subsystem, and separate sections for each piece of equipment not part of a system.



1. Dividers: Provide heavy paper dividers with celluloid-covered tabs for each separate Section. Mark each tab to indicate contents. Provide a typed description of the product and major parts of equipment included in the Section on each divider.
- C. Organize data into three-ring binders with identification on front and spine of each binder, and envelopes for folded drawings. Identify each binder on the front and spine with the printed title "OPERATION AND MAINTENANCE MANUAL", Project title or name, year and subject matter covered. Indicate volume number for multiple volume sets of manuals. Include the following:
 1. Manufacturer's operation and maintenance documentation.
 2. Maintenance and service schedules.
 3. Maintenance service contracts. Include name and telephone number of service agent.
 4. Emergency instructions.
 5. Spare parts list and local sources of maintenance materials.
 6. Wiring diagrams.
 7. Copies of warranties. Include procedures to follow and required notifications for warranty claims

2.3 RECORD DRAWINGS

- A. Record Prints: Maintain a set of prints of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued. Mark to show actual installation where installation varies from that shown originally. Accurately record information in an acceptable drawing technique.
 1. Identify and date each record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.
- B. Record Digital Data Files: Immediately before inspection for Certificate of Substantial Completion, review marked-up record prints with Engineer. When authorized, prepare a full set of corrected digital data files of the Contract Drawings.
 1. Format: Annotated PDF electronic file.



PART 3 - EXECUTION

3.1 EXAMINATION AND PREPARATION

- A. Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance.
 - 1. Verify compatibility with and suitability of substrates.
 - 2. Examine roughing-in for mechanical and electrical systems.
 - 3. Examine walls, floors, and roofs for suitable conditions.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.
- C. Take field measurements as required to fit the Work properly. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication.
- D. Verify space requirements and dimensions of items shown diagrammatically on Drawings.

3.2 CONSTRUCTION LAYOUT

- A. Before proceeding to lay out the Work, verify layout information shown on Drawings.

3.3 INSTALLATION

- A. Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
 - 1. Make vertical work plumb and make horizontal work level.
 - 2. Conceal wiring in finished areas unless otherwise indicated.
 - 3. Maintain minimum headroom clearance of 96 inches in occupied spaces and 90 inches in unoccupied spaces.
- B. Comply with manufacturer's written instructions and recommendations.
- C. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.



- D. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed.
- E. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place. Where size and type of attachments are not indicated, verify size and type required for load conditions.
 - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Owner.
- F. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.
- G. Use products, cleaners, and installation materials that are not considered hazardous.

3.4 CUTTING AND PATCHING

- A. Provide temporary support of work to be cut.
- B. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- C. Where existing services/systems are required to be removed, relocated, or abandoned, bypass such services/systems before cutting to prevent interruption to occupied areas.
- D. Cutting: Cut in-place construction using methods least likely to damage elements retained or adjoining construction.
 - 1. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
- E. Patch with durable seams that are as invisible as possible. Provide materials and comply with installation requirements specified in other Sections.
 - 1. Restore exposed finishes of patched areas and extend finish restoration into adjoining construction in a manner that will minimize evidence of patching and refinishing.



2. Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance.
3. Where patching occurs in a painted surface, prepare substrate and apply primer and intermediate paint coats appropriate for substrate over the patch, and apply final paint coat over entire unbroken surface containing the patch. Provide additional coats until patch blends with adjacent surfaces.

3.5 CLEANING

- A. Clean Project site and work areas daily, including common areas. Dispose of materials lawfully.
 1. Remove liquid spills promptly.
 2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.
 3. Remove debris from concealed spaces before enclosing the space.
- B. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion:
 1. Clean Project site and grounds, in areas disturbed by construction activities. Sweep paved areas; remove stains, spills, and foreign deposits. Rake grounds that are neither planted nor paved to a smooth, even-textured surface.
 2. Sweep paved areas broom clean. Remove spills, stains, and other foreign deposits.
 3. Remove labels that are not permanent.
 4. Clean transparent materials, including mirrors. Remove excess glazing compounds.
 5. Clean exposed finishes to a dust-free condition, free of stains, films, and foreign substances. Sweep concrete floors broom clean.
 6. Vacuum carpeted surfaces.
 7. Wipe surfaces of mechanical and electrical equipment. Remove excess lubrication and foreign substances. Clean plumbing fixtures. Clean light fixtures, lamps, globes, and reflectors.

3.6 OPERATION AND MAINTENANCE MANUAL PREPARATION

- A. Operation and Maintenance Manuals: Assemble a complete set of operation and maintenance data indicating operation and maintenance of each system, subsystem, and piece of equipment not part of a system.



- B. Manufacturers' Data: Where manuals contain manufacturers' standard printed data, include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.
 - 1. Prepare supplementary text if manufacturers' standard printed data are unavailable and where the information is necessary for proper operation and maintenance of equipment or systems.
- C. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams.

3.7 DEMONSTRATION AND TRAINING

- A. Contractor to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system. Include a detailed review of the following:
 - 1. Include instruction for basis of system design and operational requirements, review of documentation, emergency procedures, operations, adjustments, troubleshooting, maintenance, and repairs.
- B. Contractor shall train Owner's teaching faculty on the online monitoring functionality of new system.

END OF SECTION 01 7000



SECTION 01 7419 - CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 - GENERAL (Not Used)

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 PLAN IMPLEMENTATION

- A. General: Provide handling, containers, storage, signage, transportation, and other items as required to implement waste management plan during the entire duration of the Contract.
- B. Training: Train workers, subcontractors, and suppliers on proper waste management procedures, as appropriate for the Work occurring at Project site.
 - 1. Review locations established for recycling and disposal.

3.2 RECYCLING WASTE

- A. Packaging:
 - 1. Cardboard and Boxes: Break down packaging into flat sheets. Bundle and store in a dry location.
 - 2. Polystyrene Packaging: Separate and bag materials.
 - 3. Pallets: As much as possible, require deliveries using pallets to remove pallets from Project site. For pallets that remain on-site, break down pallets into component wood pieces and comply with requirements for recycling wood.
 - 4. Crates: Break down crates into component wood pieces and comply with requirements for recycling wood.
- B. Wood Materials:
 - 1. Sort and stack reusable members according to size, type, and length. Separate lumber, engineered wood products, panel products, and treated wood materials.
 - 2. Clean Cut-Offs of Lumber: Grind or chip into small pieces.
 - 3. Clean Sawdust: Bag sawdust that does not contain painted or treated wood.
- C. Metals: Separate metals by type.



3.3 DISPOSAL OF WASTE

- A. Except for items or materials to be recycled or otherwise reused, remove waste materials from Project site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.
- B. Recycle recyclable materials off-site.
- C. Do not burn waste materials.

END OF SECTION 01 7419

DIVISION 22 – ELECTRICAL

Section 26 0519 – Low-Voltage Electrical Power Conductors and Cables

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Building wires and cables rated 600 V and less.
 - 2. Connectors, splices, and terminations rated 600 V and less.

PART 2 - PRODUCTS

2.1 CONDUCTORS AND CABLES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Alpha Wire Company.
 - 2. Belden Inc.
 - 3. Cerro Wire LLC.
 - 4. Cooper Industries, Inc.
 - 5. Encore Wire Corporation.
 - 6. General Cable Technologies Corporation.
 - 7. General Cable; General Cable Corporation.
 - 8. Senator Wire & Cable Company.
 - 9. Service Wire Co.
 - 10. Southwire Company.
 - 11. Thomas & Betts Corporation, A Member of the ABB Group.
- B. Copper Conductors: Comply with NEMA WC 70/ICEA S-95-658.
- C. Conductor Insulation: Comply with NEMA WC 70/ICEA S-95-658 for Type THHN/THWN-2.

2.2 CONNECTORS AND SPLICES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - 1. 3M.
 - 2. AFC Cable Systems, Inc.
 - 3. Gardner Bender.
 - 4. Hubbell Power Systems, Inc.

5. Ideal Industries, Inc.
6. ILSCO.
7. NSi Industries LLC.
8. O-Z/Gedney; a brand of Emerson Industrial Automation.
9. Tyco Electronics Corp.

- B. Description: Factory-fabricated connectors and splices of size, ampacity rating, material, type, and class for application and service indicated.
 1. Expandable steel spring and polypropylene body type connectors and wire nuts for wire sizes up to an including No. 10 AWG.
 2. Bolt type connectors or mechanical compression crimp type for wire sizes No. 8 AWG and larger. Cover connectors with three layers of 600 volt tape or heat shrinkable insulation equivalent to 150% conductor insulation.

2.3 SYSTEM DESCRIPTION

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NFPA 70.

PART 3 - EXECUTION

3.1 CONDUCTOR MATERIAL APPLICATIONS

- A. Feeders: Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
- B. Branch Circuits: Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger, except VFC cable, which shall be extra flexible stranded.

3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

- A. Service Entrance: Type THHN/THWN-2, single conductors in raceway.
- B. Exposed Branch Circuits, Including in Crawlspace: Type THHN/THWN-2, single conductors in raceway.
- C. Minimum wire size shall be No. 12 except for internal fixture wire which shall be minimum size of No. 14 type SF, SFF, PF, PFF or TFN, 600 volt.
- D. All branch circuit wiring and feeder cables for circuits over 20 amps shall be sized as noted on the drawings. If size is not specifically noted, size all branch circuit wiring and feeder cables in accordance with the National Electrical Code.

3.3 INSTALLATION OF CONDUCTORS AND CABLES

- A. Complete raceway installation between conductor and cable termination points according to Section 260533 "Raceways and Boxes for Electrical Systems" prior to pulling conductors and cables.

- B. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- C. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.
- D. Support cables according to Section 260529 "Hangers and Supports for Electrical Systems."

3.4 CONNECTIONS

- A. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A-486B.
- B. Make splices, terminations, and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.
- C. Splices and taps in conductors shall be as few in number as practicable.
- D. Splices and taps shall be so made that they have an electrical resistance not in excess of that of 2' of the conductor.
 - 1. Use oxide inhibitor in each splice, termination, and tap for aluminum conductors.

3.5 IDENTIFICATION

- A. Identify and color-code conductors and cables according to Section 260553 "Identification for Electrical Systems."
- B. Identify each spare conductor at each end with identity number and location of other end of conductor, and identify as spare conductor.

END OF SECTION 26 0519

DIVISION 22 – ELECTRICAL
Section 26 0526 – Grounding and Bonding for Electrical Systems

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes grounding and bonding systems and equipment.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Burndy; Part of Hubbell Electrical Systems.
 - 2. Dossert; AFL Telecommunications LLC.
 - 3. ERICO International Corporation.
 - 4. Fushi Copperweld Inc.
 - 5. Galvan Industries, Inc.; Electrical Products Division, LLC.
 - 6. Harger Lightning & Grounding.
 - 7. ILSCO.
 - 8. O-Z/Gedney; a brand of Emerson Industrial Automation.
 - 9. Robbins Lightning, Inc.
 - 10. Siemens Power Transmission & Distribution, Inc.

2.2 SYSTEM DESCRIPTION

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with UL 467 for grounding and bonding materials and equipment.

2.3 CONDUCTORS

- A. Insulated Conductors: Copper or tinned-copper wire or cable insulated for 600 V unless otherwise required by applicable Code or authorities having jurisdiction.

B. Bare Copper Conductors:

1. Solid Conductors: ASTM B 3.

2.4 CONNECTORS

- A. Listed and labeled by an NRTL acceptable to authorities having jurisdiction for applications in which used and for specific types, sizes, and combinations of conductors and other items connected.
- B. Welded Connectors: Exothermic-welding kits of types recommended by kit manufacturer for materials being joined and installation conditions.

2.5 GROUNDING ELECTRODES

- A. Ground Rods: Copper-clad steel; 3/4 inch by 10 feet.

PART 3 - EXECUTION

3.1 APPLICATIONS

- A. Conductors: Install solid conductor for No. 8 AWG and smaller, and stranded conductors for No. 6 AWG and larger unless otherwise indicated.
- B. Underground Grounding Conductors: Install barecopper conductor, No. 2/0 AWG minimum.
 1. Bury at least 24 inches below grade.
- C. Conductor Terminations and Connections:
 1. Underground Connections: Welded connectors except at test wells and as otherwise indicated.

3.2 EQUIPMENT GROUNDING

- A. Install insulated equipment grounding conductors with all feeders and branch circuits. Separate grounding conductors are not shown on the drawings but shall be included in all raceways as set forth on the drawings.

3.3 INSTALLATION

- A. Grounding Conductors: Route along shortest and straightest paths possible unless otherwise indicated or required by Code. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.
- B. Ground Rods: Drive rods until tops are 2 inches below finished floor or final grade unless otherwise indicated.

1. Interconnect ground rods with grounding electrode conductor below grade and as otherwise indicated. Make connections without exposing steel or damaging coating if any.

END OF SECTION 26 0526

DIVISION 22 – ELECTRICAL
Section 26 0529 – Hangers and Supports for Electrical Systems

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Hangers and supports for electrical equipment and systems.
 - 2. Construction requirements for concrete bases.

PART 2 - PRODUCTS

2.1 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Steel Slotted Support Systems: Comply with MFMA-4 factory-fabricated components for field assembly.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Allied Tube & Conduit; a part of Atkore International.
 - b. Cooper B-Line, Inc.; a division of Cooper Industries.
 - c. ERICO International Corporation.
 - d. Flex-Strut Inc.
 - e. GS Metals Corp.
 - f. G-Strut.
 - g. Haydon Corporation.
 - h. Metal Ties Innovation.
 - i. Thomas & Betts Corporation, A Member of the ABB Group.
 - j. Unistrut; an Atkore International company.
 - 2. Material: Galvanized steel.
 - 3. Channel Width: 1-5/8 inches.
 - 4. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
- B. Conduit and Cable Support Devices: Steel hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- C. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for nonarmored electrical conductors or cables in riser conduits. Plugs shall have number, size, and shape of conductor gripping pieces as

required to suit individual conductors or cables supported. Body shall be made of malleable iron.

- D. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:
1. Powder-Actuated Fasteners: Anchors using explosive charges to drive inserts into concrete shall not be used.
 2. Clamps for Attachment to Steel Structural Elements: MSS SP-58 units are suitable for attached structural element.
 3. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM A 325.
 4. Toggle Bolts: All-steel springhead type.
 5. Hanger Rods: Threaded steel.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Comply with NECA 1 and NECA 101 for application of hangers and supports for electrical equipment and systems unless requirements in this Section are stricter.
- B. Comply with requirements for raceways and boxes specified in Section 260533 "Raceways and Boxes for Electrical Systems."
- C. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway: Space supports for EMTs, IMCs, and RMCs as required by NFPA 70. Minimum rod size shall be 1/4 inch in diameter.

3.2 SUPPORT INSTALLATION

- A. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:
1. To Steel: Beam clamps (MSS SP-58, Type 19, 21, 23, 25, or 27), complying with MSS SP-69 or metal framing channel welded to structure.
 2. To Light Steel: Sheet metal screws.
 3. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate[**by means that comply with seismic-restraint strength and anchorage requirements**].
- B. Drill holes for expansion anchors in concrete at locations and to depths that avoid the need for reinforcing bars.

3.3 CONCRETE BASES

- A. Construct concrete bases of dimensions indicated.
- B. Use 3000-psi, 28-day compressive-strength concrete.

- C. Anchor equipment to concrete base as follows:
 - 1. Place and secure anchorage devices. Use supported equipment manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - 2. Install anchor bolts to elevations required for proper attachment to supported equipment.
 - 3. Install anchor bolts according to anchor-bolt manufacturer's written instructions.
- D. Provide concrete bases for the following floor mounted equipment:
 - 1. Generators.

END OF SECTION 26 0529

DIVISION 22 – ELECTRICAL
Section 26 0533 – Raceways and Boxes for Electrical Systems

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Metal conduits, tubing, and fittings.
 - 2. Nonmetal conduits, tubing, and fittings.
 - 3. Boxes, enclosures, and cabinets.

1.3 DEFINITIONS

- A. GRC: Galvanized rigid steel conduit.

PART 2 - PRODUCTS

2.1 METAL CONDUITS, TUBING, AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. AFC Cable Systems, Inc.
 - 2. Allied Tube & Conduit; a part of Atkore International.
 - 3. Anamet Electrical, Inc.
 - 4. Electri-Flex Company.
 - 5. FSR Inc.
 - 6. O-Z/Gedney; a brand of Emerson Industrial Automation.
 - 7. Patriot Aluminum Products, LLC.
 - 8. Picoma Industries, Inc.
 - 9. Republic Conduit.
 - 10. Robroy Industries.
 - 11. Southwire Company.
 - 12. Thomas & Betts Corporation, A Member of the ABB Group.
 - 13. Western Tube and Conduit Corporation.
- B. Listing and Labeling: Metal conduits, tubing, and fittings shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. GRC: Comply with ANSI C80.1 and UL 6.
- D. EMT: Comply with ANSI C80.3 and UL 797.

- E. FMC: Comply with UL 1; zinc-coated steel.
- F. LFMC: Flexible steel conduit with PVC jacket and complying with UL 360.
- G. Fittings for Metal Conduit: Comply with NEMA FB 1 and UL 514B.
 - 1. Fittings for EMT:
 - a. Material: Steel.
 - b. Type: Compression.
- H. Joint Compound for IMC, GRC, or ARC: Approved, as defined in NFPA 70, by authorities having jurisdiction for use in conduit assemblies, and compounded for use to lubricate and protect threaded conduit joints from corrosion and to enhance their conductivity.

2.2 NONMETALLIC CONDUITS, TUBING, AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. AFC Cable Systems, Inc.
 - 2. Anamet Electrical, Inc.
 - 3. Arnco Corporation.
 - 4. CANTEX INC.
 - 5. CertainTeed Corporation.
 - 6. Condux International, Inc.
 - 7. Electri-Flex Company.
 - 8. Kraloy.
 - 9. Lamson & Sessions.
 - 10. Niedax Inc.
 - 11. RACO; Hubbell.
- B. Listing and Labeling: Nonmetallic conduits, tubing, and fittings shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. ENT: Comply with NEMA TC 13 and UL 1653.
- D. RNC: Type EPC-40-PVC, complying with NEMA TC 2 and UL 651 unless otherwise indicated.
- E. LFNC: Comply with UL 1660.
- F. Fittings for ENT and RNC: Comply with NEMA TC 3; match to conduit or tubing type and material.
- G. Fittings for LFNC: Comply with UL 514B.

2.3 BOXES, ENCLOSURES, AND CABINETS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Adalet.

2. Cooper Technologies Company.
 3. EGS/Appleton Electric.
 4. Erickson Electrical Equipment Company.
 5. FSR Inc.
 6. Hoffman; a brand of Pentair Equipment Protection.
 7. Hubbell Incorporated.
 8. Kraloy.
 9. Milbank Manufacturing Co.
 10. MonoSystems, Inc.
 11. Oldcastle Enclosure Solutions.
 12. O-Z/Gedney; a brand of Emerson Industrial Automation.
 13. RACO; Hubbell.
 14. Robroy Industries.
 15. Spring City Electrical Manufacturing Company.
 16. Stahlin Non-Metallic Enclosures.
 17. Thomas & Betts Corporation, A Member of the ABB Group.
- B. General Requirements for Boxes, Enclosures, and Cabinets: Boxes, enclosures, and cabinets installed in wet locations shall be listed for use in wet locations.
- C. Sheet Metal Outlet and Device Boxes: Comply with NEMA OS 1 and UL 514A.
- D. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- E. Device Box Dimensions: 4 inches square by 2-1/8 inches deep.
- F. Gangable boxes are prohibited.

PART 3 - EXECUTION

3.1 RACEWAY APPLICATION

- A. Outdoors: Apply raceway products as specified below unless otherwise indicated:
1. Exposed Conduit: GRC.
 2. Underground Conduit: RNC, Type EPC-40-PVC,.
 3. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC.
 4. Boxes and Enclosures, Aboveground: NEMA 250, Type 3R.
- B. Indoors: Apply raceway products as specified below unless otherwise indicated:
1. Exposed, Not Subject to Physical Damage: EMT.
 2. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC.
Boxes and Enclosures: NEMA 250, Type 1.
- C. Minimum Raceway Size: 3/4-inch trade size.
- D. Raceway Fittings: Compatible with raceways and suitable for use and location.
1. Rigid Conduit: Use threaded rigid steel conduit fittings unless otherwise indicated. Comply with NEMA FB 2.10.

2. EMT: Use compression, steel fittings. Comply with NEMA FB 2.10.
3. Flexible Conduit: Use only fittings listed for use with flexible conduit. Comply with NEMA FB 2.20.

3.2 INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except where requirements on Drawings or in this article are stricter. Comply with NECA 102 for aluminum conduits. Comply with NFPA 70 limitations for types of raceways allowed in specific occupancies and number of floors.
- B. Keep raceways at least 6 inches away from parallel runs of flues and steam or hot-water pipes. Install horizontal raceway runs above water and steam piping.
- C. Complete raceway installation before starting conductor installation.
- D. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for hangers and supports.
- E. Conduits and raceways shall not be supported from plumbing lines, ductwork or supports for equipment provided by other trades.
- F. Arrange stub-ups so curved portions of bends are not visible above finished slab.
- G. Install no more than the equivalent of three 90-degree bends in any conduit run except for control wiring conduits, for which fewer bends are allowed. Support within 12 inches of changes in direction.
- H. Support conduit within 12 inches of enclosures to which attached.
- I. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of raceway and fittings before making up joints. Follow compound manufacturer's written instructions.
- J. Coat field-cut threads on PVC-coated raceway with a corrosion-preventing conductive compound prior to assembly.
- K. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install bushings on conduits up to 1-1/4-inch trade size and insulated throat metal bushings on 1-1/2-inch trade size and larger conduits terminated with locknuts. Install insulated throat metal grounding bushings on service conduits.
- L. Install raceways square to the enclosure and terminate at enclosures with locknuts. Install locknuts hand tight plus 1/4 turn more.
- M. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to assembling conduit to enclosure to assure a continuous ground path.
- N. Cut conduit perpendicular to the length. For conduits 2-inch trade size and larger, use roll cutter or a guide to make cut straight and perpendicular to the length.
- O. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb tensile strength. Leave at least 12 inches of slack at each end of pull wire. Cap underground raceways designated as spare above grade alongside raceways in use.

- P. Install raceway sealing fittings at accessible locations according to NFPA 70 and fill them with listed sealing compound. For concealed raceways, install each fitting in a flush steel box with a blank cover plate having a finish similar to that of adjacent plates or surfaces. Install raceway sealing fittings according to NFPA 70.
- Q. Install devices to seal raceway interiors at accessible locations. Locate seals so no fittings or boxes are between the seal and the following changes of environments. Seal the interior of all raceways at the following points:
 - 1. Where conduits pass from warm to cold locations, such as boundaries of refrigerated spaces.
 - 2. Where an underground service raceway enters a building or structure.
 - 3. Where otherwise required by NFPA 70.
- R. Comply with manufacturer's written instructions for solvent welding RNC and fittings.

3.3 INSTALLATION OF UNDERGROUND CONDUIT

- A. Direct-Buried Conduit:
 - 1. Excavate trench bottom to provide firm and uniform support for conduit.
 - 2. After installing conduit, backfill and compact. Start at tie-in point, and work toward end of conduit run, leaving conduit at end of run free to move with expansion and contraction as temperature changes during this process. Firmly hand tamp backfill around conduit to provide maximum supporting strength. After placing controlled backfill to within 12 inches of finished grade, make final conduit connection at end of run and complete backfilling with normal compaction.
 - 3. Install manufactured rigid steel conduit elbows for stub-ups at poles and equipment and at building entrances through floor.
 - a. Couple steel conduits to ducts with adapters designed for this purpose, and encase coupling with 3 inches of concrete for a minimum of 12 inches on each side of the coupling.
 - b. For stub-ups at equipment mounted on outdoor concrete bases and where conduits penetrate building foundations, extend steel conduit horizontally a minimum of 60 inches from edge of foundation or equipment base. Install insulated grounding bushings on terminations at equipment.
 - 4. Underground Warning Tape: Comply with requirements in Section 260553 "Identification for Electrical Systems."

3.4 PROTECTION

- A. Protect coatings, finishes, and cabinets from damage and deterioration.
 - 1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
 - 2. Repair damage to PVC coatings or paint finishes with matching touchup coating recommended by manufacturer.

- B. Protect work from injury by keeping all conduit and boxes capped and plugged or otherwise protected. This includes damage by freezing and / or stoppage from building materials, sand, dirt or concrete.

END OF SECTION 26 0533

Section 26 0544 – Sleeves and Sleeve Seals for Electrical Raceways and Cabling

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Sleeve-seal systems.
 - 2. Silicone sealants.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 SLEEVE-SEAL SYSTEMS

- A. Description: Modular sealing device, designed for field assembly, to fill annular space between sleeve and raceway or cable.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Advance Products & Systems, Inc.
 - b. CALPICO, Inc.
 - c. Metraflex Company (The).
 - d. Pipeline Seal and Insulator, Inc.
 - 2. Sealing Elements: EPDM rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
 - 3. Pressure Plates: Stainless steel.
 - 4. Connecting Bolts and Nuts: Stainless steel of length required to secure pressure plates to sealing elements.

2.2 SILICONE SEALANTS

- A. Silicone Sealants: Single-component, silicone-based, neutral-curing elastomeric sealants of grade indicated below.

1. Grade: Pourable (self-leveling) formulation for openings in floors and other horizontal surfaces that are not fire rated.
- B. Silicone Foams: Multicomponent, silicone-based liquid elastomers that, when mixed, expand and cure in place to produce a flexible, nonshrinking foam.

PART 3 - EXECUTION

3.1 SLEEVE-SEAL-SYSTEM INSTALLATION

- A. Install sleeve-seal systems in sleeves in exterior walls and slabs-on-grade at raceway entries into building.
- B. Install type and number of sealing elements recommended by manufacturer for raceway or cable material and size. Position raceway or cable in center of sleeve. Assemble mechanical sleeve seals and install in annular space between raceway or cable and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.

END OF SECTION 26 0544

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Identification for raceways.
 - 2. Identification of power and control cables.
 - 3. Identification for conductors.
 - 4. Underground-line warning tape.
 - 5. Warning labels and signs.
 - 6. Instruction signs.
 - 7. Equipment identification labels, including arc-flash warning labels.
 - 8. Miscellaneous identification products.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for electrical identification products.
- B. Samples: For each type of label and sign to illustrate composition, size, colors, lettering style, mounting provisions, and graphic features of identification products.
- C. Identification Schedule: For each piece of electrical equipment and electrical system components to be an index of nomenclature for electrical equipment and system components used in identification signs and labels. Use same designations indicated on Drawings.
- D. Delegated-Design Submittal: For arc-flash hazard study.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Comply with NFPA 70.

2.2 TAPES AND STENCILS:

- A. Underground-Line Warning Tape

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Brady Corporation.
 - b. Ideal Industries, Inc.
 - c. LEM Products Inc.
 - d. Marking Services, Inc.
 - e. Reef Industries, Inc.
2. Tape:
 - a. Recommended by manufacturer for the method of installation and suitable to identify and locate underground electrical and communications utility lines.
 - b. Printing on tape shall be permanent and shall not be damaged by burial operations.
 - c. Tape material and ink shall be chemically inert and not subject to degradation when exposed to acids, alkalis, and other destructive substances commonly found in soils.
3. Color and Printing:
 - a. Comply with ANSI Z535.1, ANSI Z535.2, ANSI Z535.3, ANSI Z535.4, and ANSI Z535.5.
 - b. Inscriptions for Red-Colored Tapes: "ELECTRIC LINE ".
4. Tape Construction:
 - a. Detectable three-layer laminate, consisting of a printed pigmented polyolefin film, a solid aluminum-foil core, and a clear protective film that allows inspection of the continuity of the conductive core; bright colored, continuous-printed on one side with the inscription of the utility, compounded for direct-burial service.
 - b. Width: 3 inches.
 - c. Overall Thickness: 5 mils.
 - d. Foil Core Thickness: 0.35 mil.
 - e. Tensile according to ASTM D 882: 70 lbf and 4600 psi.

2.3 SIGNS

A. Laminated Acrylic or Melamine Plastic Signs:

1. Engraved legend.
2. Thickness:
 - a. 1/8 inch thick.
 - b. Engraved legend with black letters on white face.
 - c. Punched or drilled for mechanical fasteners.
 - d. Framed with mitered acrylic molding and arranged for attachment at applicable equipment.
3. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Brady Corporation.
 - b. Carlton Industries, LP.

- c. emedco.

2.4 MISCELLANEOUS IDENTIFICATION PRODUCTS

- A. Fasteners for Labels and Signs: Self-tapping, stainless-steel screws or stainless-steel machine screws with nuts and flat and lock washers.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Verify and coordinate identification names, abbreviations, colors, and other features with requirements in other Sections requiring identification applications, Drawings, Shop Drawings, manufacturer's wiring diagrams, and operation and maintenance manual. Use consistent designations throughout Project.
- B. Install identifying devices before installing acoustical ceilings and similar concealment.
- C. Verify identity of each item before installing identification products.
- D. Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment. Install access doors or panels to provide view of identifying devices.
- E. Apply identification devices to surfaces that require finish after completing finish work.
- F. Attach signs and plastic labels that are not self-adhesive type with mechanical fasteners appropriate to the location and substrate.
- G. During backfilling of trenches, install continuous underground-line warning tape directly above cable or raceway at 6 to 8 inches below finished grade. Use multiple tapes where width of multiple lines installed in a common trench or concrete envelope exceeds 16 inches overall.

3.2 IDENTIFICATION SCHEDULE

- A. Power-Circuit Conductor Identification, 600 V or Less: For conductors in vaults, pull and junction boxes, manholes, and handholes, use color-coding conductor tape to identify the phase.
 - 1. Color-Coding for Phase- and Voltage-Level Identification, 600 V or Less: Use colors listed below for ungrounded service feeder and branch-circuit conductors.
 - a. Color shall be factory applied or field applied for sizes larger than No. 8 AWG if authorities having jurisdiction permit.
 - b. Colors for 208/120-V Circuits:
 - 1) Phase A: Black.
 - 2) Phase B: Red.
 - 3) Phase C: Blue.
 - 4) Neutral: White.
 - 5) Ground: Green.

- c. Field-Applied, Color-Coding Conductor Tape: Apply in half-lapped turns for a minimum distance of 6 inches from terminal points and in boxes where splices or taps are made. Apply last two turns of tape with no tension to prevent possible unwinding. Locate bands to avoid obscuring factory cable markings.
- B. Locations of Underground Lines: Identify with underground-line warning tape for power, lighting, communication, and control wiring and optical-fiber cable.
 - 1. Install underground-line warning tape for direct-buried cables and cables in raceways.
- C. Equipment Identification Labels: On each unit of equipment, install unique designation label that is consistent with wiring diagrams, schedules, and operation and maintenance manual. Apply labels to disconnect switches and protection equipment, central or master units, control panels, control stations, terminal cabinets, and racks of each system. Systems include power, lighting, control, communication, signal, monitoring, and alarm unless equipment is provided with its own identification.
 - 1. Labeling Instructions:
 - a. Indoor Equipment: Engraved, laminated acrylic or melamine plastic label, punched or drilled for mechanical fasteners. Unless otherwise indicated, provide a single line of text with 1/2-inch-high letters on 1-1/2-inch-high label; where two lines of text are required, use labels 2 inches high.
 - b. Fasten labels with appropriate mechanical fasteners that do not change the NEMA or NRTL rating of the enclosure.
 - c. Attach labels with screws and not adhesives.
 - 2. Equipment To Be Labeled:
 - a. Transfer switches.

END OF SECTION 26 0553

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes packaged engine-generator sets for standby power supply with the following features:
 - 1. Diesel engine.
 - 2. Unit-mounted cooling system.
 - 3. Unit-mounted control and monitoring.
 - 4. Fuel system.
 - 5. Outdoor enclosure.
- B. Related Requirements:
 - 1. Section 26 3600 "Transfer Switches" for transfer switches including sensors and relays to initiate automatic-starting and -stopping signals for engine-generator sets.

1.3 DEFINITIONS

- A. Operational Bandwidth: The total variation from the lowest to highest value of a parameter over the range of conditions indicated, expressed as a percentage of the nominal value of the parameter.
- B. LP: Liquid petroleum.
- C. EPS: Emergency power supply.
- D. EPSS: Emergency power supply system.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
 - 2. Include thermal damage curve for generator.
 - 3. Include time-current characteristic curves for generator protective device.
 - 4. Include fuel consumption in gallons per hour at 0.8 power factor at 0.5, 0.75 and 1.0 times generator capacity.
 - 5. Include generator efficiency at 0.8 power factor at 0.5, 0.75 and 1.0 times generator capacity.

6. Include air flow requirements for cooling and combustion air in cfm at 0.8 power factor, with air supply temperature of 95, 80, 70, and 50 deg F. Provide drawings showing requirements and limitations for location of air intake and exhausts.
7. Include generator characteristics, including, but not limited to kw rating, efficiency, reactances, and short-circuit current capability.

B. Shop Drawings:

1. Include plans and elevations for engine-generator set and other components specified. Indicate access requirements affected by height of subbase fuel tank.
2. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Identify fluid drain ports and clearance requirements for proper fluid drain.
4. Design calculations for selecting vibration isolators and seismic restraints and for designing vibration isolation bases.
5. Include diagrams for power, signal, and control wiring. Complete schematic, wiring, and interconnection diagrams showing terminal markings for EPS equipment and functional relationship between all electrical components.

1.5 INFORMATIONAL SUBMITTALS

A. Source quality-control reports, including, but not limited to the following:

1. Certified summary of prototype-unit test report.
2. Certified Test Reports: For components and accessories that are equivalent, but not identical, to those tested on prototype unit.

B. Field quality-control reports.

C. Warranty: For special warranty.

1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For packaged engine generators to include in emergency, operation, and maintenance manuals.

1. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:
 - a. List of tools and replacement items recommended to be stored at Project for ready access. Include part and drawing numbers, current unit prices, and source of supply.
 - b. Operating instructions laminated and mounted adjacent to generator location.
 - c. Training plan.

1.7 WARRANTY

A. Manufacturer's Warranty: Manufacturer agrees to repair or replace components of packaged engine generators and associated auxiliary components that fail in materials or workmanship within specified warranty period.

1. Warranty Period: two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 1. Generac Power Systems (Basis of Design)
 2. Cummins Power Generation
 3. Kohler Power Systems
- B. Source Limitations: Obtain packaged generator sets and auxiliary components through one source from a single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

- A. ASME Compliance: Comply with ASME B15.1.
- B. NFPA Compliance:
 1. Comply with NFPA 37.
 2. Comply with NFPA 70.
- C. UL Compliance: Comply with UL 2200.
- D. Engine Exhaust Emissions: Comply with EPA Tier 3 requirements and applicable state and local government requirements.
- E. Environmental Conditions: Engine-generator system shall withstand the following environmental conditions without mechanical or electrical damage or degradation of performance capability:
 1. Ambient Temperature: Minus 15 to plus 40 deg C.
 2. Relative Humidity: Zero to 95 percent.
 3. Altitude: Sea level to 1000 feet.

2.3 ASSEMBLY DESCRIPTION

- A. Factory-assembled and -tested, water-cooled engine, with brushless generator and accessories.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a testing agency acceptable to authorities having jurisdiction, and marked for intended location and application.
- C. Governor: Adjustable isochronous, with speed sensing.
- D. Emissions: Comply with EPA Tier 3 requirements.

- E. Mounting Frame: Structural steel framework to maintain alignment of mounted components without depending on concrete foundation. Provide lifting attachments sized and spaced to prevent deflection of base during lifting and moving.
- F. Capacities and Characteristics:
 - 1. Power Output Ratings: Nominal ratings as indicated at 0.8 power factor excluding power required for the continued and repeated operation of the unit and auxiliaries.
 - 2. Output Connections: Three-phase, four wire.
 - 3. Nameplates: For each major system component to identify manufacturer's name and address, and model and serial number of component.
- G. Generator-Set Performance:
 - 1. **200kW minimum generator engine with an alternator capable of starting a minimum 450 skVA at a maximum 20% Vdip.**
 - 2. Steady-State Voltage Operational Bandwidth: 3 percent of rated output voltage from no load to full load.
 - 3. Transient Voltage Performance: Not more than 20 percent variation for 50 percent step-load increase or decrease. Voltage shall recover and remain within the steady-state operating band within three seconds.
 - 4. Steady-State Frequency Operational Bandwidth: 0.5 percent of rated frequency from no load to full load.
 - 5. Steady-State Frequency Stability: When system is operating at any constant load within the rated load, there shall be no random speed variations outside the steady-state operational band and no hunting or surging of speed.
 - 6. Transient Frequency Performance: Less than 5 percent variation for 50 percent step-load increase or decrease. Frequency shall recover and remain within the steady-state operating band within five seconds.
 - 7. Output Waveform: At no load, harmonic content measured line to line or line to neutral shall not exceed 5 percent total and 3 percent for single harmonics. Telephone influence factor, determined according to NEMA MG 1, shall not exceed 50 percent.
 - 8. Sustained Short-Circuit Current: For a three-phase, bolted short circuit at system output terminals, system shall supply a minimum of 250 percent of rated full-load current for not less than 10 seconds and then clear the fault automatically, without damage to generator system components.

2.4 ENGINE

- A. Fuel: Fuel oil, Grade DF-2.
- B. Rated Engine Speed: 1800 rpm.
- C. Maximum Piston Speed for Four-Cycle Engines: 2250 fpm.
- D. Lubrication System: The following items are mounted on engine or skid:
 - 1. Filter and Strainer: Rated to remove 90 percent of particles 5 micrometers and smaller while passing full flow.
 - 2. Thermostatic Control Valve: Control flow in system to maintain optimum oil temperature. Unit shall be capable of full flow and is designed to be fail-safe.
 - 3. Crankcase Drain: Arranged for complete gravity drainage to an easily removable container with no disassembly and without use of pumps, siphons, special tools, or appliances.

- E. Jacket Coolant Heater: Electric-immersion type, factory installed in coolant jacket system. Comply with NFPA 110 requirements for Level 1 equipment for heater capacity.
- F. Cooling System: Closed loop, liquid cooled, with radiator factory mounted on engine-generator-set mounting frame and integral engine-driven coolant pump.
 - 1. Coolant: Solution of 50 percent ethylene-glycol-based antifreeze and 50 percent water, with anticorrosion additives as recommended by engine manufacturer.
 - 2. Size of Radiator: Adequate to contain expansion of total system coolant from cold start to 110 percent load condition.
 - 3. Temperature Control: Self-contained, thermostatic-control valve modulates coolant flow automatically to maintain optimum constant coolant temperature as recommended by engine manufacturer.
 - 4. Coolant Hose: Flexible assembly with inside surface of nonporous rubber and outer covering of aging-, ultraviolet-, and abrasion-resistant fabric.
 - a. Rating: 50-psig maximum working pressure with coolant at 180 deg F, and noncollapsible under vacuum.
 - b. End Fittings: Flanges or steel pipe nipples with clamps to suit piping and equipment connections.
- G. Muffler/Silencer: Commercial type, sized as recommended by engine manufacturer and selected with exhaust piping system to not exceed engine manufacturer's engine backpressure requirements.
- H. Air-Intake Filter: Heavy-duty, engine-mounted air cleaner with replaceable dry-filter element and "blocked filter" indicator.
- I. Starting System: 24-V electric, with negative ground.
 - 1. Components: Sized so they are not damaged during a full engine-cranking cycle with ambient temperature at maximum specified in "Performance Requirements" Article.
 - 2. Cranking Motor: Heavy-duty unit that automatically engages and releases from engine flywheel without binding.
 - 3. Cranking Cycle: 60 seconds.
 - 4. Battery: Lead acid, with capacity within ambient temperature range specified in "Performance Requirements" Article to provide specified cranking cycle at least three times without recharging.
 - 5. Battery Cable: Size as recommended by engine manufacturer for cable length indicated. Include required interconnecting conductors and connection accessories.
 - 6. Battery Stand: Factory-fabricated, two-tier metal with acid-resistant finish designed to hold the quantity of battery cells required and to maintain the arrangement to minimize lengths of battery interconnections.
 - 7. Battery-Charging Alternator: Factory mounted on engine with solid-state voltage regulation and 35 A minimum continuous rating.
 - 8. Battery Charger: Current-limiting, automatic-equalizing and float-charging type designed for lead-acid batteries. Unit shall comply with UL 1236 and include the following features:
 - a. Operation: Equalizing-charging rate of 10 A shall be initiated automatically after battery has lost charge until an adjustable equalizing voltage is achieved at battery terminals. Unit shall then be automatically switched to a lower float-charging mode and shall continue to operate in that mode until battery is discharged again.
 - b. Automatic Temperature Compensation: Adjust float and equalize voltages for variations in ambient temperature from minus 40 deg F to 140 deg F to prevent overcharging at high temperatures and undercharging at low temperatures.

- c. Automatic Voltage Regulation: Maintain constant output voltage regardless of input voltage variations up to plus or minus 10 percent.
- d. Ammeter and Voltmeter: Flush mounted in door. Meters shall indicate charging rates.

2.5 DIESEL FUEL-OIL SYSTEM

- A. Comply with NFPA 30.
- B. Piping: Fuel-oil piping shall be Schedule 40 black steel, complying with requirements in Section 231113 "Facility Fuel-Oil Piping." Cast iron, aluminum, copper, and galvanizing shall not be used in the fuel-oil system.
- C. Main Fuel Pump: Mounted on engine to provide primary fuel flow under starting and load conditions.
- D. Fuel Filtering: Remove water and contaminants larger than 1 micron.
- E. Relief-Bypass Valve: Automatically regulates pressure in fuel line and returns excess fuel to source.
- F. Subbase-Mounted, Double-Wall, Fuel-Oil Tank: Factory installed and piped, complying with UL 142 fuel-oil tank. Features include the following:
 - 1. Tank level indicator.
 - 2. Fuel-Tank Capacity: 24 hour runtime at 100% load, minimum.
 - 3. Leak detection in interstitial space.
 - 4. Vandal-resistant fill cap.
 - 5. Containment Provisions: Comply with requirements of authorities having jurisdiction.

2.6 CONTROL AND MONITORING

- A. Automatic Starting System Sequence of Operation: When mode-selector switch on the control and monitoring panel is in the automatic position, remote-control contacts in one or more separate automatic transfer switches initiate starting and stopping of generator set. When mode-selector switch is switched to the on position, generator set starts. The off position of same switch initiates generator-set shutdown. When generator set is running, specified system or equipment failures or derangements automatically shut down generator set and initiate alarms.
- B. Provide minimum run time control set for 15 minutes with override only by operation of a remote emergency-stop switch.
- C. Comply with UL 508A.
- D. Configuration: Operating and safety indications, protective devices, basic system controls, and engine gages shall be grouped in a common control and monitoring panel mounted on the generator set. Mounting method shall isolate the control panel from generator-set vibration. Panel shall be powered from the engine-generator set battery.
- E. Indicating Devices: Including the following:
 - 1. AC voltmeter.

2. AC ammeter.
 3. AC frequency meter.
 4. EPS supplying load indicator.
 5. Ammeter and voltmeter phase-selector switches.
 6. DC voltmeter (alternator battery charging).
 7. Engine-coolant temperature gage.
 8. Engine lubricating-oil pressure gage.
 9. Running-time meter.
 10. Current and Potential Transformers: Instrument accuracy class.
- F. Supporting Items: Include sensors, transducers, terminals, relays, and other devices and include wiring required to support specified items. Locate sensors and other supporting items on engine or generator, unless otherwise indicated.
- G. Common Remote Panel with Common Audible Alarm: Include necessary contacts and terminals in control and monitoring panel. Remote panel shall be powered from the engine-generator set battery.
- H. Remote Alarm Annunciator: An LED labeled with proper alarm conditions shall identify each alarm event, and a common audible signal shall sound for each alarm condition. Silencing switch in face of panel shall silence signal without altering visual indication. Connect so that after an alarm is silenced, clearing of initiating condition will reactivate alarm until silencing switch is reset. Cabinet and faceplate are surface- or flush-mounting type to suit mounting conditions indicated.
1. Overcrank alarm.
 2. Coolant low-temperature alarm.
 3. High engine temperature prealarm.
 4. High engine temperature alarm.
 5. Low lube oil pressure alarm.
 6. Overspeed alarm.
 7. Low fuel main tank alarm.
 8. Low coolant level alarm.
 9. Low cranking voltage alarm.
 10. Contacts for local and remote common alarm.
 11. Audible-alarm silencing switch.
 12. Air shutdown damper when used.
 13. Run-Off-Auto switch.
 14. Control switch not in automatic position alarm.
 15. Generator overcurrent protective device not closed.
- I. Supporting Items: Include sensors, transducers, terminals, relays, and other devices and include wiring required to support specified items. Locate sensors and other supporting items on engine or generator, unless otherwise indicated.
- J. Remote Emergency-Stop Switch: Flush; wall mounted, unless otherwise indicated; and labeled. Push button shall be protected from accidental operation.

2.7 GENERATOR OVERCURRENT AND FAULT PROTECTION

- A. Generator Circuit Breaker: Molded-case, thermal-magnetic type; 100 percent rated; complying with UL 489.
1. Rated for 600 A Tripping Characteristic: Designed specifically for generator protection.

2. Trip Rating: Matched to generator output rating.
3. Shunt Trip: Connected to trip breaker when generator set is shut down by other protective devices.
4. Mounting: Adjacent to or integrated with control and monitoring panel.

2.8 GENERATOR, EXCITER, AND VOLTAGE REGULATOR

- A. Comply with NEMA MG 1.
- B. Drive: Generator shaft shall be directly connected to engine shaft. Exciter shall be rotated integrally with generator rotor.
- C. Electrical Insulation: Class F.
- D. Stator-Winding Leads: Brought out to terminal box to permit future reconnection for other voltages if required. Provide six lead alternator.
- E. Range: Provide limited range of output voltage by adjusting the excitation level.
- F. Construction shall prevent mechanical, electrical, and thermal damage due to vibration, overspeed up to 125 percent of rating, and heat during operation at 110 percent of rated capacity.
- G. Enclosure: Dripproof.
- H. Instrument Transformers: Mounted within generator enclosure.
- I. Voltage Regulator: Solid-state type, separate from exciter.
 1. Adjusting Rheostat on Control and Monitoring Panel: Provide plus or minus 5 percent adjustment of output-voltage operating band.
 2. Maintain voltage within 20 percent on one step, full load.
 3. Provide anti-hunt provision to stabilize voltage.
 4. Maintain frequency within 5 percent and stabilize at rated frequency within 5 seconds.
- J. Strip Heater: Thermostatically controlled unit arranged to maintain stator windings above dew point.

2.9 OUTDOOR GENERATOR-SET ENCLOSURE

- A. Description: Vandal-resistant, weatherproof steel housing, wind resistant up to 100 mph. Multiple panels shall be lockable and provide adequate access to components requiring maintenance. Panels shall be removable by one person without tools. Instruments and control shall be mounted within enclosure. Maximum sound emission at 7 meters shall not exceed 35 dBA.
- B. Engine Cooling Airflow through Enclosure: Maintain temperature rise of system components within required limits when unit operates at 110 percent of rated load for 2 hours with ambient temperature at top of range specified in system service conditions.
 1. Louvers: Fixed-engine, cooling-air inlet and discharge. Storm-proof and drainable louvers prevent entry of rain and snow.

- C. Convenience Outlets: Factory wired, GFCI. Arrange for external electrical connection.

2.10 FINISHES

- A. Indoor and Outdoor Enclosures and Components: Manufacturer's standard finish over corrosion-resistant pretreatment and compatible primer.

2.11 SOURCE QUALITY CONTROL

- A. Prototype Testing: Factory test engine-generator set using same engine model, constructed of identical or equivalent components and equipped with identical or equivalent accessories.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas, equipment bases, and conditions, with Installer present, for compliance with requirements for installation and other conditions affecting packaged engine-generator performance.
- B. Examine roughing-in for electrical connections. Verify actual locations of connections before packaged engine-generator installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Interruption of Existing Electrical Service:
 - 1. Notify Engineer no fewer than five working days in advance of proposed interruption of electrical service.

3.3 INSTALLATION

- A. Comply with packaged engine-generator manufacturers' written installation and alignment instructions.
- B. Equipment Mounting:
 - 1. Install packaged engine generators on cast-in-place concrete equipment bases.
 - 2. Coordinate size and location of concrete bases for packaged engine generators. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified with concrete.
- C. Install packaged engine-generator to provide access, without removing connections or accessories, for periodic maintenance.
- D. Electrical Wiring: Install electrical devices furnished by equipment manufacturers but not specified to be factory mounted.

3.4 CONNECTIONS

- A. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."
- B. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables." Provide a minimum of one 90 degree bend in flexible conduit routed to the generator set from a stationary element.

3.5 IDENTIFICATION

- A. Identify system components according to Section 230553 "Identification for HVAC Piping and Equipment" and Section 260553 "Identification for Electrical Systems."
- B. Install a sign indicating the generator neutral is bonded to the main service neutral at the main service location.

3.6 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
 - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections.
- B. Tests and Inspections:
 - 1. Perform tests recommended by manufacturer and each visual and mechanical inspection and electrical and mechanical test listed in the first two subparagraphs as specified in NETA Acceptance Testing Specification. Certify compliance with test parameters.
 - a. Visual and Mechanical Inspection
 - 1) Compare equipment nameplate data with drawings and specifications.
 - 2) Inspect physical and mechanical condition.
 - 3) Inspect anchorage, alignment, and grounding.
 - 4) Verify the unit is clean.
 - b. Electrical and Mechanical Tests
 - 1) Verify phase rotation, phasing, and synchronized operation as required by the application.
 - 2) Functionally test engine shutdown for low oil pressure, overtemperature, overspeed, and other protection features as applicable.
 - 3) Verify correct functioning of the governor and regulator.
 - 2. Battery Tests: Equalize charging of battery cells according to manufacturer's written instructions. Record individual cell voltages.
 - a. Measure charging voltage and voltages between available battery terminals for full-charging and float-charging conditions. Check electrolyte level and specific gravity under both conditions.
 - b. Test for contact integrity of all connectors. Perform an integrity load test and a capacity load test for the battery.

- c. Verify acceptance of charge for each element of the battery after discharge.
 - d. Verify that measurements are within manufacturer's specifications.
 - 3. Battery-Charger Tests: Verify specified rates of charge for both equalizing and float-charging conditions.
 - 4. System Integrity Tests: Methodically verify proper installation, connection, and integrity of each element of engine-generator system before and during system operation. Check for air, exhaust, and fluid leaks.
 - C. Coordinate tests with tests for transfer switches and run them concurrently.
 - D. Test instruments shall have been calibrated within the last 12 months, traceable to NIST Calibration Services, and adequate for making positive observation of test results. Make calibration records available for examination on request.
 - E. Leak Test: After installation, charge exhaust, coolant, and fuel systems and test for leaks. Repair leaks and retest until no leaks exist.
 - F. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation for generator and associated equipment.
 - G. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
 - H. Remove and replace malfunctioning units and reinspect as specified above.
 - I. Retest: Correct deficiencies identified by tests and observations and retest until specified requirements are met.
 - J. Report results of tests and inspections in writing. Record adjustable relay settings and measured insulation resistances, time delays, and other values and observations. Attach a label or tag to each tested component indicating satisfactory completion of tests.
- 3.7 DEMONSTRATION
- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain packaged engine generators.

END OF SECTION 26 3213

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes automatic transfer switches rated 600 V and less.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for transfer switches.
 - 2. Include rated capacities, operating characteristics, electrical characteristics, and accessories.
- B. Shop Drawings:
 - 1. Include plans, elevations, sections, details showing minimum clearances, conductor entry provisions, gutter space, and installed features and devices.
 - 2. Include material lists for each switch specified.
 - 3. Single-Line Diagram: Show connections between transfer switch, power sources, and load; and show interlocking provisions for each combined transfer switch and bypass/isolation switch.

1.4 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For each type of product to include in emergency, operation, and maintenance manuals.

1.6 FIELD CONDITIONS

- A. Interruption of Existing Electrical Service: Do not interrupt electrical service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary electrical service:

1. Notify Engineer no fewer than five days in advance of proposed interruption of electrical service.

1.7 WARRANTY

- A. Manufacturer's Warranty: Manufacturer agrees to repair or replace components of transfer switch or transfer switch components that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NEMA ICS 1.
- C. Comply with UL 1008 unless requirements of these Specifications are stricter.
- D. Indicated Current Ratings: Apply as defined in UL 1008 for continuous loading and total system transfer, including tungsten filament lamp loads not exceeding 30 percent of switch ampere rating, unless otherwise indicated.
- E. Tested Fault-Current Closing and Short-Circuit Ratings: Adequate for duty imposed by protective devices at installation locations in Project under the fault conditions indicated, based on testing according to UL 1008.
- F. Repetitive Accuracy of Solid-State Controls: All settings shall be plus or minus 2 percent or better over an operating temperature range of minus 20 to plus 70 deg C.
- G. Resistance to Damage by Voltage Transients: Components shall meet or exceed voltage-surge withstand capability requirements when tested according to IEEE C62.62. Components shall meet or exceed voltage-impulse withstand test of NEMA ICS 1.
- H. Electrical Operation: Accomplish by a nonfused, momentarily energized solenoid or electric-motor-operated mechanism. Switches for emergency or standby purposes shall be mechanically and electrically interlocked in both directions to prevent simultaneous connection to both power sources unless closed transition.
- I. Service-Rated Transfer Switch:
 1. **Transfer switch shall be 3-pole and rated for 600A at 120/208V, 3Ph.**
 2. Comply with UL 869A and UL 489.
 3. Provide terminals for bonding the grounding electrode conductor to the grounded service conductor.
 4. In systems with a neutral, the bonding connection shall be on the neutral bus.
 5. Provide removable link for temporary separation of the service and load grounded conductors.
 6. Service Disconnecting Means: Externally operated, manual mechanically actuated.

- J. Neutral Terminal: Solid and fully rated unless otherwise indicated.
- K. Factory Wiring: Train and bundle factory wiring and label, consistent with Shop Drawings, by color-code or by numbered or lettered wire and cable markers at terminations. Color-coding and wire and cable markers are specified in Section 260553 "Identification for Electrical Systems."
- L. Enclosures: General-purpose NEMA 250, Type 1, complying with NEMA ICS 6 and UL 508, unless otherwise indicated.
- M. Metering Package: Switch shall come equipped with a digital read out of the following: Load-side voltage, frequency and power readings (Energy - real, reactive, apparent (Wh, VAR, VAh))

2.2 CONTACTOR-TYPE AUTOMATIC TRANSFER SWITCHES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Generac Power Systems, Inc. (Basis of design)
 - 2. Cummins Power Generation.
 - 3. Kohler Power Systems.
- B. Switch Characteristics: Designed for continuous-duty repetitive transfer of full-rated current between active power sources.
 - 1. Switch Action: Double throw; mechanically held in both directions.
 - 2. Contacts: Silver composition or silver alloy for load-current switching. Contactor-style automatic transfer-switch units, rated 600 A and higher, shall have separate arcing contacts.
 - 3. Conductor Connectors: Suitable for use with conductor material and sizes.
 - 4. Material: Hard-drawn copper, 98 percent conductivity.
 - 5. Main and Neutral Lugs: Compression type.
 - 6. Ground Lugs and Bus-Configured Terminators: Compression type.
 - 7. Ground bar.
 - 8. Connectors shall be marked for conductor size and type according to UL 1008.
- C. Automatic Open-Transition Transfer Switches: Interlocked to prevent the load from being closed on both sources at the same time.
 - 1. Sources shall be mechanically and electrically interlocked to prevent closing both sources on the load at the same time.
- D. Manual Switch Operation: Under load, with door closed and with either or both sources energized. Transfer time is same as for electrical operation. Control circuit automatically disconnects from electrical operator during manual operation.
- E. Automatic Transfer-Switch Controller Features:
 - 1. Controller operates through a period of loss of control power.
 - 2. Undervoltage Sensing for Each Phase of Normal Source: Sense low phase-to-ground voltage on each phase. Pickup voltage shall be adjustable from 85 to 100 percent of nominal, and dropout voltage shall be adjustable from 75 to 98 percent of pickup value. Factory set for pickup at 90 percent and dropout at 85 percent.
 - 3. Voltage/Frequency Lockout Relay: Prevent premature transfer to generator. Pickup voltage shall be adjustable from 85 to 100 percent of nominal. Factory set for pickup at

- 90 percent. Pickup frequency shall be adjustable from 90 to 100 percent of nominal. Factory set for pickup at 95 percent.
4. Time Delay for Retransfer to Normal Source: Adjustable from zero to 30 minutes, and factory set for 10 minutes. Override shall automatically defeat delay on loss of voltage or sustained undervoltage of emergency source, provided normal supply has been restored.
 5. Test Switch: Simulate normal-source failure.
 6. Switch-Position Pilot Lights: Indicate source to which load is connected.
 7. Source-Available Indicating Lights: Supervise sources via transfer-switch normal- and emergency-source sensing circuits.
 - a. Normal Power Supervision: Green light with nameplate engraved "Normal Source Available."
 - b. Emergency Power Supervision: Red light with nameplate engraved "Emergency Source Available."
 8. Unassigned Auxiliary Contacts: Two normally open, single-pole, double-throw contacts for each switch position, rated 10 A at 240-V ac.
 9. Transfer Override Switch: Overrides automatic retransfer control so transfer switch will remain connected to emergency power source regardless of condition of normal source. Pilot light indicates override status.
 10. Engine Starting Contacts: One isolated and normally closed, and one isolated and normally open; rated 10 A at 32-V dc minimum.
 11. Engine Shutdown Contacts: Time delay adjustable from zero to five minutes, and factory set for five minutes. Contacts shall initiate shutdown at remote engine-generator controls after retransfer of load to normal source.
 12. Engine-Generator Exerciser: Solid-state, programmable-time switch starts engine generator and transfers load to it from normal source for a preset time, then retransfers and shuts down engine after a preset cool-down period. Initiates exercise cycle at preset intervals adjustable from 7 to 30 days. Running periods shall be adjustable from 10 to 30 minutes. Factory settings shall be for 7-day exercise cycle, 20-minute running period, and 5-minute cool-down period. Exerciser features include the following:
 - a. Exerciser Transfer Selector Switch: Permits selection of exercise with and without load transfer.
 - b. Push-button programming control with digital display of settings.
 - c. Integral battery operation of time switch when normal control power is unavailable.

2.3 SOURCE QUALITY CONTROL

- A. Factory Tests: Test and inspect components, assembled switches, and associated equipment according to UL 1008. Ensure proper operation. Check transfer time and voltage, frequency, and time-delay settings for compliance with specified requirements. Perform dielectric strength test complying with NEMA ICS 1.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Identify components according to Section 260553 "Identification for Electrical Systems."
- B. Set field-adjustable intervals and delays, relays, and engine exerciser clock.

- C. Comply with NECA 1.

3.2 CONNECTIONS

- A. Wiring to Remote Components: Match type and number of cables and conductors to generator sets, control, and communication requirements of transfer switches as recommended by manufacturer. Increase raceway sizes at no additional cost to Owner if necessary to accommodate required wiring.
- B. Wiring Method: Install cables in raceways and cable trays except within electrical enclosures. Conceal raceway and cables except in unfinished spaces.
 - 1. Comply with requirements for raceways and boxes specified in Section 260533 "Raceways and Boxes for Electrical Systems."
- C. Wiring within Enclosures: Bundle, lace, and train conductors to terminal points with no excess and without exceeding manufacturer's limitations on bending radii.
- D. Ground equipment according to Section 260526 "Grounding and Bonding for Electrical Systems."
- E. Connect wiring according to Section 260519 "Low-Voltage Electrical Power Conductors and Cables" and Section 271500 "Communications Horizontal Cabling."
- F. Final connections to equipment shall be made with liquidtight, flexible metallic conduit no more than 18 inches in length.

3.3 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections with the assistance of a factory-authorized service representative:
 - 1. After installing equipment, test for compliance with requirements according to NETA ATS.
 - 2. Visual and Mechanical Inspection:
 - a. Compare equipment nameplate data with Drawings and Specifications.
 - b. Inspect physical and mechanical condition.
 - c. Inspect anchorage, alignment, grounding, and required clearances.
 - d. Verify that the unit is clean.
 - e. Verify appropriate lubrication on moving current-carrying parts and on moving and sliding surfaces.
 - f. Verify that manual transfer warnings are attached and visible.
 - g. Verify tightness of all control connections.
 - h. Inspect bolted electrical connections for high resistance using one of the following methods, or both:
 - 1) Use of low-resistance ohmmeter.
 - 2) Verify tightness of accessible bolted electrical connections by calibrated torque-wrench method according to manufacturer's published data.
 - i. Perform manual transfer operation.
 - j. Verify positive mechanical interlocking between normal and alternate sources.
 - k. Perform visual and mechanical inspection of surge arresters.

- I. Inspect control power transformers.
 - 1) Inspect for physical damage, cracked insulation, broken leads, tightness of connections, defective wiring, and overall general condition.
 - 2) Verify that primary and secondary fuse or circuit-breaker ratings match Drawings.
 - 3) Verify correct functioning of drawout disconnecting contacts, grounding contacts, and interlocks.

3. Electrical Tests:
 - a. Verify settings and operation of control devices.
 - b. Calibrate and set all relays and timers.
 - c. Verify phase rotation, phasing, and synchronized operation.
 - d. Perform automatic transfer tests.
 - e. Verify correct operation and timing of the following functions:
 - 1) Normal source voltage-sensing and frequency-sensing relays.
 - 2) Engine start sequence.
 - 3) Time delay on transfer.
 - 4) Alternative source voltage-sensing and frequency-sensing relays.
 - 5) Automatic transfer operation.
 - 6) Interlocks and limit switch function.
 - 7) Time delay and retransfer on normal power restoration.
 - 8) Engine cool-down and shutdown feature.

4. After energizing circuits, perform each electrical test for transfer switches stated in NETA ATS and demonstrate interlocking sequence and operational function for each switch at least three times.
 - a. Simulate power failures of normal source to automatic transfer switches and retransfer from emergency source with normal source available.
 - b. Simulate loss of phase-to-ground voltage for each phase of normal source.
 - c. Verify time-delay settings.
 - d. Verify pickup and dropout voltages by data readout or inspection of control settings.
 - e. Test bypass/isolation unit functional modes and related automatic transfer-switch operations.
 - f. Verify proper sequence and correct timing of automatic engine starting, transfer time delay, retransfer time delay on restoration of normal power, and engine cool-down and shutdown.

- B. Coordinate tests with tests of generator and run them concurrently.

- C. Report results of tests and inspections in writing. Record adjustable relay settings and measured insulation and contact resistances and time delays. Attach a label or tag to each tested component indicating satisfactory completion of tests.

- D. Transfer switches will be considered defective if they do not pass tests and inspections.

- E. Remove and replace malfunctioning units and retest as specified above.

- F. Prepare test and inspection reports.

3.4 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain transfer switches and related equipment.
- B. Training shall include testing ground-fault protective devices and instructions to determine when the ground-fault system shall be retested. Include instructions on where ground-fault sensors are located and how to avoid negating the ground-fault protection scheme during testing and circuit modifications.
- C. Coordinate this training with that for generator equipment.

END OF SECTION 26 3600